

INDIAN INSTITUTE OF TECHNOLOGY KANPUR
INSTITUTE WORKS DEPARTMENT
ELECTRICAL & AIR-CONDITIONING DIVISION

No. 18/AC/EE/2020/228

Dated 13-10-2020

QUOTATION NOTICE

M/s

Sealed quotations are invited from the empanelled contractors/Specialized agencies by the undersigned on behalf of the Director, IIT Kanpur for **“Repairing & Repainting of electrical main panel and replacement of defective spare parts i.e digital display, touch keypad panel, programming including other associated works etc. For CESE Building AC Plant..”** As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 22-10-2020 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 28(Twenty Eight) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
4. Security @ 7.5% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. The estimated cost of quotation is **Rs.129918/-**. The required earnest money of **Rs. 2600/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per approved list of make.


QUOTATION

Sub: Repairing & Repainting of electrical main panel and replacement of defective spare parts i.e digital display, touch keypad panel, programming including other associated works etc. For CESE Building AC Plant.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
Part A					
1	SITC of Temperature Sensor MCS (Part No: 56.101.50.025) of 75 TR water cooled chiller unit	1	Nos.		
2	Supply installation testing and commissioning touch keypad control panel	1	No.		
3	Supply installation testing and commissioning of MCS -8 digital display with backlight 120X32 Display	1	No.		
4	Service, re-programming charges for repair of main controller MCS -8 etc. complete as reqd	1	No.		
Part B					
1	Cleaning and servicing of 250 Amp, floor mounted electrical starter panel for Painting (inbuilt 250 Amp I/c, 250 Amp busbar with 04 Nos. 5.0 HP DOL starters and 10 HP star delta starters i/c metering panel) removing all existing switchgears/spares and refitting the same after cleaning, washing by petrol/diesel, modification, fabrication for new spares painting, tagging assembly fitting, testing, commissioning	1	Job		
2	S & F of 40 to 63 amp rating 4 pole 415 volt MCB in the existing MCB DB complete with connection, testing & commissioning etc as reqd.	1	Nos.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
3	Supply, laying, affecting connections and Testing of the following sizes of 1.1 KV Un armoured PVC insulated copper conductor cables. Cables shall be inclusive of all clamps,saddles,screws,cable identification tags, cable terminal joints including terminal lugs, insulating tapes, affecting terminal connections to the equipment as per the specifications and as required.				
a)	4 x 16 sqmm	12	Mtr		
4	Supply & fixing of power connector (63 Amp) etc. complete as reqd.	2	No.		
5	Providing & fixing of push button with elements complete as reqd.	2	No.		
6	Providing & fixing of indicators (ON/off/ trip) complete as reqd.	1	Nos.		
7	P & F of door lock with key . complete as reqd..	2	No.		
8	Providing & fixing of control & power wiring in existing panel including all DOL/star-delta starter and metering panel by copper wire lugs, tag, tape thimble, etc. complete as reqd.	1	Job		
9	Providing and fixing of door gasket for electrical panel using proper chemical/ adhesive including removing of old gasket from panel door complete as reqd.	1	Job		

Total Rs.


 रघुवेंद्र सिंह
 RAGHVENDRA SINGH
 अधिष्ठात्री अभियंता (वि०) E.E. (Elect.)
 संवि० वि०, भा० प्रौ० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur