

## QUOTATION

**Name of work** - Repairing / Replacement damaged of street lights in swimming pool as per enclosed complaints.


S.No.	Description of Items	Qty	Unit	Rate	Amount
				(In Words & Figures)	
1	Numbering of ceiling fan/ exhaust fan/ fluorescent fittings as required.	15.00	Each		
2	S & F of following rating & poles 240 volts 'C' curve 10 kA MCB in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a)	Single Pole (5A to 32A)	15.00	Nos.		
b	Double Pole (40A to 63A)	1.00	Nos.		
3	S&F, connecting and commissioning looping type cable end control box with MS sheet of 16 SWG of size 200 mm x 200 mm x 125 mm having 1 no. 6amp to 32 amp SPMCB 250 volt and 2 nos. brass neutral link 12.5 mm square rod 6 way approx. 60 mm long and fixed on 5 mm thick bakelite sheet. Box shall have almirah type hing and panel key type lock front door duly painted with earthing strud etc. complete as required.	4.00	Nos.		
4	Dismantling damaged switch/DB/KWH meter/ all type fitting / ceiling fan / Exhaust fan/ Wall Fan / pole fuse box/TPN switches metal helide box with MCB/Pole fuse box and depositing in the section store.	13.00	Nos.		
5	Supplying and drawing of following sizes of FRLS PVC insulated copper conductor, 3 core round cable of following size in the existing surface/ recessed steel/ PVC conduit as required.				
a	1.5 Sq.mm	50.00	Mtr		
6	Supplying,fixing,testing commissioning of garden light 35W LED postop lantern Luminures. New generation, post-top, energy saving, environmental friendly, long life aesthetically designed with symmetrical light distribution, spun aluminium landscape luminaire with high power LEDs as light source. make:havells or its equivalent, on the existing pole complete as required.	9.00	Nos.		

S.No.	Description of Items	Qty	Unit	Rate	Amount
-------	----------------------	-----	------	------	--------

(In Words & Figures)

7	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.				
a	upto 35 sqmm	2.00	Nos.		
8	Dismantling and refixing brass compression type gland up to 35 sq. mm. cable	8.00	Nos.		
9	Digging cable trench/lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	10.00	Mtr.		

Total Rs

  
 Ravendra Singh  
 अधिसायी अभियन्ता (वि०)/E.E. (Elect.)  
 मंत्रालय, भा० प्रौ० संस्थान, कानपुर  
 I.W.D., I.I.T., Kanpur  
