


QUOTATION

Name of work :- Rewinding and overhauling of ceiling fans installed at H.No.-2041, 2070, 2100, 413, 4005 & 242 etc.

S.No.	Description of work	Qty.	Unit	Rate (In words & Figures)	Amount
1	Rewinding of following fans of following sizes i/c dismantling of rotor cutting the damaged winding and providing rewinding along with insulation paper, varnish, connecting copper leads of suitable quality including dismentling and refixing from normal/abnormal height and refixing as required. (Old burnt wire shall be reatin by the contractor.)				
a)	New model 48"/wall fan	4.00	Nos.		
b)	Old model 48"/new mode 56"	3.00	Nos.		
2	Overhauling of ceiling fan of any size including dismantling and refixing of fan, bearings, checking, cleaning the all parts and supplying & replacement of rubber real, rubber rings, nut bolts, hanger clamps, bearing plates, cotter/ split pin, varnishing if reqd etc, reassembling testing and commissioning of fan as required complete.				
a)	ceiling fan / wall fan	48.00	Nos.		
3	Supplying and fixing 2.5 mfd capacitor suitable for ceiling fan.	18.00	Nos.		
4	Repairing of housing of bearing side /bush side /in fan body in ceiling fan /exhaust fan/ rally fan etc.	8.00	Nos.		
5	Painting of ceiling fan any size with one or more coats with supper enamel paint of approved brand i/c cleaning and making smooth surface with emery paper and detergent etc. as required.	16.00	Nos.		
6	Balancing of ceiling fan blade of any size including making suitable shape of twisted blades at site	1.00	Nos.		
7	Cartage of Ceiling fans and regulator / exhaust fan From store to site as reqd.	48.00	Nos.		

S.No.	Description of work	Qty.	Unit	Rate (In words & Figures)	Amount
8	Supply of following size ball bearings.				
a)	Ball bearing 6201 (NBC - make)	1.00	Nos.		
b)	Ball bearing 6202 (NBC - make)	1.00	Nos.		

Total


रघुवेंद्र सिंह
RAGHVENDRA SINGH
 अधिष्ठापी अभियंता (वि०) E.E. (Elect)
 सं० नि० वि० का० वि०, राणपुर, का० पु०
 I.W.E., L.M.T., Ranpur
