

INDIAN INSTITUTE OF TECHNOLOGY KANPUR  
INSTITUTE WORKS DEPARTMENT  
ELECTRICAL & AIR-CONDITIONING DIVISION

No. 24/AC/EE/2021/194

Dated 09-11-2021

QUOTATION NOTICE

M/s .....

Sealed quotations are invited from the specialized agency/empanelled contractor by the undersigned on behalf of the Director, IIT Kanpur for **“Half body fabrication of water coolers and replacement of compressor cold room with other associated works (i.e condenser unit, drier filter, contractor etc) at Security control room, IIT main gate, central workshop & Hall-X etc..”** As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 17-11-2021 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

11. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
12. The time allowed for carrying out the above noted work is 21(Twenty One) Days.
13. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
14. Security @ 7.5% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
15. The estimated cost of quotation is **Rs.48040/-**. The required earnest money of **Rs. 961/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
16. The quotations shall remain valid for 90 days from the date of opening.
17. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
18. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
19. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
20. The material should be used as per approved list of make.

**QUOTATION**

**Sub: Half body fabrication of water coolers and replacement of compressor cold room with other associated works (i.e condenser unit, drier filter, contractor etc) at Security control room , IIT main gate, central workshop & Hall-X etc.**

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Half body fabrication of water cooler body 150/150 Ltrs capacity 18 Gauge/20 Gauge GI sheet with base frame duly painted and complete in all respect complete as reqd.	3.00	Nos		
2	Supplying, fixing, testing & commissioning of new compressor of following capacity i/c. dismantling of defective compressor (returnable to the supplier on rebate basis) of following make Kirloskar/ Tecum/ Carrier/ Hitachi.				
a)	1.5 TR Capacity	1.00	No.		
3	Supply and fixing condenser unit housing for water cooler/refrigerator of 150 Litrs.capacity of size as reqd. (complete).	3.00	Nos		
4	Providing & fixing of Drier filter size suitable of cold room etc. complete as reqd.	1.00	No.		
5	Providing & fixing of single phase contractor suitable for split/window/cold room type air conditioner units of approved make etc. complete as reqd.				
a)	30 Amp	1.00	No.		
6	Rewinding of existing condenser fan motor of following equipment, with super enamelled cu-wire of approved make, i/c dismantling & fixing of motor to the existing unit as reqd. (complete).				
a)	Cold Room/Window AC	2.00	No.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
7	Spray painting of water cooler 150 litres capacity Freezer/ Deep freezer 300/ 400 Ltr capacity after denting work of small patches, scrubbing old paint, painting with one coat of primer and two coat of super enamel paint of approved brand manufacture as required.	2.00	Nos		
8	Gas charging in split/tower/ window & water cooler type air-conditioner of following capacity after leak testing, evacuation, with replacement of capillary & liquid line strainer as reqd. (complete).				
a)	Cold Room	1.00	No.		
9	Servicing of following equipment (i.e.- dismantling ,cleaning, lubricating, re-fitting,testing & commissioning the unit) with cleaning the filters, cooling & condensing coils by removing dust, washing with approved condenser coil cleaner & finally wash with fresh water, lubricating the fan motor , denting work & painting of window ac, i/c. refitting of window ac by using auto wire,pvc tape,thimbles,m/c. screws,washers,nut ,bolts, etc.as required (complete).				
a)	Cold Room	1.00	Nos.		

Total- Rs. \_\_\_\_\_



सहायक संचालक (सं) ए.ए. (A.C.)  
 महाराष्ट्र शासन, वित्त, वसाहती, वसाहती  
 (W.D., L.I., Kharpur)