

INDIAN INSTITUTE OF TECHNOLOGY KANPUR
INSTITUTE WORKS DEPARTMENT
ELECTRICAL & AIR-CONDITIONING DIVISION

No. 28/AC/EE/2021/201

Dated 17-11-2021

QUOTATION NOTICE

M/s
.....
.....
.....

Sealed quotations are invited from the empanelled contractor by the undersigned on behalf of the Director, IIT Kanpur for "**Providing and Fixing exhaust fans in Reading room, common room Ground & 1st Floor with associated works at Hall-11...**" As per enclosed Bill of Quantity/overleaf, so as to reach in this office on or before 24-11-2021 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 21(Twenty One) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
4. Security @ 7.5% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. The estimated cost of quotation is **Rs.50949/-**. The required earnest money of **Rs. 1020/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per approved list of make.


QUOTATION

Sub: Providing and Fixing exhaust fans in Reading room, common room Ground & 1st Floor with associated works at Hall-11.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	3 x 1.5 sq.mm	50	Mtrs.		
2	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.				
a)	75 mm X 75 mm X 60 mm deep	7	Nos.		
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a)	5/6 A switch	7	Nos.		
4	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	7	Nos.		
5	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a)	1 or 2 Module (75mmX75mm)	7	Nos.		
6	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	7	Nos.		
7	Providing & fixing of size 32 mm x 12.5 mm. DLP mini trunking system with independent cover as reqd.	45	Mtrs.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
8	Providing & fixing accessories for following size of DLP mini trunking system as reqd. (32 mm x 12.5 mm.)				
a)	Flat junction	5	Nos.		
b)	Changeable flat angle	20	Nos.		
c)	Changeable internal /External angle	30	Nos.		
d)	End cap left or right	15	Nos.		
9	Supply, fixing, testing and commissioning domestic ventilation fan of following size complete as required. (Make_ Crompton or Apprv. Make)				
a)	18"	7	Nos.		
10	Supply, fixing, testing and commissioning shutter/ louvers for exhaust fan of following size complete as required. (Make_ Appr. Make)				
a)	18"	7	Nos.		
11	S & Laying of copper conductor round cable of following size and core complete as reqd.				
a)	3 x 1.5 sqmm	5	Mtrs.		

Total- Rs. _____


 अधिशासी अभियंता (वा0) E.E. (A.C.)
 संगठनवि0, मा0प्रौ0 संस्थान, कानपुर
 I W.D., I.I.T Kanpur