

QUOTATION

Name of work -: Electrical maintenance work at Faculty Apartment ,New SBRA, RA TOWER , Type-IB Type-2 Type -4 as per enclosed complaints.

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
a	Group A	3.00	Points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	1 x 1.5 Sq.mm..	95.00	Mtr.		
b	3 x 1.5 Sq.mm..	15.00	Mtr.		
c	3 x 4 Sq.mm..	55.00	Mtr.		
3	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	5/6 Amp switch	15.00	Nos.		
b	3 Pin 5/6 Amp. socket outlet	4.00	Nos.		
c	Call bell push	1.00	Nos.		
4	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
b	15/16 Amp. switch	4.00	Nos.		
c	3 Pin 5/6 Amp. socket outlet	4.00	Nos.		
d	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
e	Bell Push	1.00	Nos.		
f	Fan regulator socket type rotary step	3.00	Nos.		
g	Blanking plate	2.00	Nos.		
5	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a	4 module	1.00	Nos.		
b	6 module	2.00	Nos.		
6	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as				
a	1 or 2 module	2.00	Nos.		
b	3 module	2.00	Nos.		
7	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	5.00	Nos.		
8	Supplying and fixing brass batten/ angle holder including connection etc. as required.	9.00	Nos.		
9	Supplying and fixing call bell/ buzzer suitable for ac single phase, 230 volts, complete as required.	2.00	Nos.		
10	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				


S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
a	Fan regulator socket type rotary/dimmer	2.00	Nos.		
11	Providing and fixing following sizes of PVC casing and capping on surface				
a	25 x 16 mm	31.00	Mtr.		
12	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a	Bulk head fitting suitable for 60W GLS lamp	3.00	Nos		
13	Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required, complete etc as reqd	2.00	Nos.		
14	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a	1200 mm	3.00	Nos		
15	Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	4732.00	Sq.cm		
16	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	12.00	Nos.		

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
------	-------------	-----	------	------------------------------	--------

17	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	51.00	Nos.		
----	---	-------	------	--	--

18	Dismantling and refixing of wooden board of any sizes on surface or in recessed etc as reqd.	30.00	Nos.		
----	--	-------	------	--	--

Total Rs


 अधिकारी अभियन्ता (वि.) / T.E. (Gen.)
 नवमिडि, ११० जी० एस्०, ४११७७
 I.W.D., H. T. KENDUR
 Date