


QUOTATION

Name of work: Electrical Maimtenance work at south side residence as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (Rs) Words & Fig	Amount
1	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	71.00	Nos.		
b)	2 way 5/6 A switch	2.00	Nos.		
c)	15/16 Amp. switch	11.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	19.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	10.00	Nos.		
f)	Fan regulator socket type rotary step	19.00	Nos.		
2	Supply & fixing modular blanking plate on existng metal boxes but excluding modular plate as req.	12.00	Nos.		
3	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	1 or 2 module	2.00	Nos.		
b)	3 module	6.00	Nos.		
c)	4 module	8.00	Nos.		
d)	6 module	7.00	Nos.		
e)	8 module	2.00	Nos.		
f)	12 module	2.00	Nos.		
4	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	4.00	Nos.		
5	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1710.00	Sq.cm		
6	Dismantling and refixing of switch / socket /regulator l/c cleaning, connecting, commissioning etc as reqd.	16.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (Rs) Words & Fig	Amount
7	Supply, installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	10.00	nos.		
b)	1400 mm	1.00	Nos.		
8	Supply & fixing of 12 W surface mounted light ec.as reqd. make Havells OR equivalent approved make.	5.00	Nos.		
9	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	9.00	Nos.		
10	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	Drum light cat No.03 PV / 02 decon make or equivalent.	3.00	Nos.		
b)	Wall bracket Decon make cat. no. 0553 or equivalent.	4.00	Nos.		
c)	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	3.00	Nos.		
d)	Wall light stylo fitting 14W Havells make or equivalent.	3.00	Nos.		
11	Supply, Installation of exhaust fan, 900 rpm 220 volt AC, 50 Hz of following sweep in the existing opening I/c connection, testing, commissioning etc as reqd.		Nos.		
a)	300 mm	2.00	Nos.		
12	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.(make Havells)	1.00	Nos.		

Total Rs.


 राविवेन्द्र सिंह
 Ravindra Singh
 इलेक्ट्रिकल अभियंता (पि) / E.E. (Elect.)
 कर्मचारी कक्षा, पी.पी. संस्थान, कानपुर
 208 002, उत्तर प्रदेश, भारत
