


QUOTATION

Name of work: Providing and fixing of Automatic Changeover / Transfer Switch(ATS) for DG power supply for Mass & NMR Spectrometer lab in old core lab building in the campus.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying, fixing, connecting, testing and commissioning following rating Enclosed Automatic Transfer switch (ATS) complete as required. (Enclosed ATS, frame 3, 205A Cat. No. CK90164BS00, make L& T or equivalent as approved)				
a)	250 Amp.	1.00	Each		
2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a)	3½ X 120 sq. mm (45mm)	2.00	Each		
Total Rs.					


इंजीनियर (ई.ई.) (Elect.)
मो. नं. 9800000000, काठमान्डू
I.W.D., I.I.T., Kanpur
