

QUOTATION

Sub Repairing/replacement of defective switch & socket casing capping distribution boards, LED fittings etc, at Outreach Gent Wash Room, OCL 205C, Outreach 111 & 113, OCL 101D and different labs and offices in academic area on complaint basis.


S.No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(in Words & Figures)	
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	13.00	Metre		
b	3 x 2.5 sq. mm	10.00	Metre		
c	3 x 4 sq. mm	5.00	Metre		
2	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 Pair	15.00	Metre		
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
a	5/6 amps switch	3.00	No.		
b	15/16 A switch	1.00	No.		
c	3 pin 5/6 A socket outlet	2.00	No.		
d	6 pin 15/16 A socket outlet	1.00	No.		
4	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	17.00	No.		
b	15/16 A switch	16.00	No.		

S.No.	DESCRIPTION	QTY	UNIT	RATE (in Words & Figures)	AMOUNT
c	3 pin 5/6 A socket outlet	4.00	No.		
d	6 pin 15/16 A socket outlet	13.00	No.		
5	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2.00	No.		
6	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a	3 Module (100mmX75mm)	1.00	No.		
7	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	lor 2 Module	4.00	No.		
b	3 Module	4.00	No.		
c	6 Module	5.00	No.		
d	12 Module	1.00	No.		
8	Supplying and fixing brass batten/ angle holder including connection etc. as required.	1.00	No.		
9	Supplying and fixing 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Triple pole (5A to 32A)	1.00	No.		
b	Triple pole and neutral (5A to 32A)	1.00	No.		
c	Double Pole (40A to 63A)	1.00	Nos.		
10	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor makeas reqd complete.				

S.No.	DESCRIPTION	QTY	UNIT	RATE (in Words & Figures)	AMOUNT
a	5 Amp	1.00	Nos.		
b	15 Amp	1.00	Nos.		
11	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	6.00	Meter		
12	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	20 mm x 12 mm	5.00	Meter		
b	25 mm x 16 mm	3.00	Meter		
13	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	20.00	Meter		
14	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	1.00	Meter		
15	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	End cap	2.00	Nos.		
16	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	5.00	Meter		
17	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		
18	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	12.00	Nos.		
19	Supplying and fixing wood box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front etc as required.				

S.No.	DESCRIPTION	QTY	UNIT	RATE (In Words & Figures)	AMOUNT
a	100 mm x 100 mm	1.00	Nos.		
b	175 mm x 100 mm	1.00	Nos.		
20	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	4.00	Nos.		
b	6 Module	1.00	Nos.		
21	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
22	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
a	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	6.00	Nos.		
23	Supply and fixing of following LED light fixture with Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	1 X 20W LED tube with fitting	4.00	Nos.		
b	2 X 20W LED tube with fitting	1.00	Nos.		
c	12 watt surface mounting LED light fixture	6.00	Nos.		
d	36 watt recess mounting LED light fixture 600 x 600 mm	9.00	Nos.		
24	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
a	450 mm / 18" sweep	1.00	Nos.		
25	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	3.00	Nos.		

S.No.	DESCRIPTION	QTY	UNIT	RATE (in Words & Figures)	AMOUNT
26	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	RJ 11 Telephone socket	2.00	Nos.		
27	S&F, connecting and commissioning AC controler box with MS sheet of 16 SWG of size 200 mm x 200 mm x 125 mm having 1 no. timer 250 volt, 2 no contactor and 2 nos. brass neutral link 12.5 mm square rod 6 way approx. 60 mm long and fixed on 6 mm thick bakelite sheet. Box shall have almirah type hinge and panel key type lock front door duly painted with earthing strud etc. complete as required.	1.00	Nos.		
Total Rs.					


 कर्मचारी कर्मिकता (मि)/ए.ए. (मि)
 पुराना, बा. रो. सल्यान, काठमाडौं
 (उ.पि.) T. Karmar
