

## QUOTATION


Sub Repairing & replacement of defective lighting, switches/socket, casing & capping, distribution board BSBE Lab-5, lab-8,Hydrauliclab,T.B, SL-218C ,208C, 206C, WI-114, 210, 101A, 103A, New clean room, Biomaterial lab,WLE-112, 217, Library, FB-374, 434, 480, 618, 153, ,ACES125,Dy. Director, ACES-217,LHC,and different labs and offices in academic area etc. as per enclosed complaints at IIT Kanpur.

S.N.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
<i>(In words &amp; Figures)</i>					
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	35.00	Metre		
b	3 x 2.5 sq. mm	17.00	Metre		
c	3 x 4 sq. mm	6.00	Metre		
2	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 Pair	34.00	Metre		
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
a	5/6 amps switch	2.00	No.		
b	15/16 A switch	3.00	No.		
c	3 pin 5/6 A socket outlet	2.00	No.		
d	6 pin 15/16 A socket outlet	4.00	No.		
4	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				

S.N.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
				(In words & Figures)	
a	5/6 A switch	10.00	No.		
b	15/16 A switch	6.00	No.		
c	3 pin 5/6 A socket outlet	8.00	No.		
d	6 pin 15/16 A socket outlet	6.00	No.		
5	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	2.00	No.		
6.00	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor make as reqd complete.				
a	15 Amp	1.00	Nos.		
7.00	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	10.00	Meter		
8.00	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	50.00	Meter		
9.00	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	7.00	Nos.		
10.00	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	22.00	Nos.		

S.N.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
				(In words & Figures)	
11.00	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantelling & refixing as reqd.	2.00	Nos.		
12.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	1.00	Nos.		
b	3 Module	2.00	Nos.		
c	6 Module	6.00	Nos.		
13.00	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
a	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	72.00	Nos.		
14.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	1 X 20W Box type LED tube with fitting	1.00	Nos.		
b	2 X 20W Box type LED tube with fitting	2.00	Nos.		
c	18 watt recess 300 x 300 mm mounting LED light fixture	3.00	Nos.		
d	36 watt recess mounting LED light fixture 600 x 600 mm	12.00	Nos.		
15.00	Supply and fixing testing and commissioning of 1X10 watt LED mirror light fixture with Electronic driver, lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.(eq. To Cropmton cat. no.LCTLN-10-CDL).	1.00	Nos.		

S.N.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
(In words & Figures)					
16.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	RJ 11 Telephone socket	1.00	Nos.		
Total Rs.					_____
					_____

  
 लक्ष्मणजी अग्रियाल (पिं)/ए.ए. (ई.एच.)  
 कम्प्यूटिंग, मा० प्रौ० संस्थान, कानपुर  
 I.W.D., I.I.T. Kanpur

*Devi*