QUOTATION

Name of work :- Repairing / Replacement of street lights / flood light on main road Gate -1 IIT Kanpur.

S.No.	Description	Qty	Unit ~	Rate (in words & Figures)	Amount
1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc.with charcoal/ coke and salt as required.	1,00	Each		
2	Supplying and drawing following sizes of FR-LSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	1 x 16 Sqmm.	15.00	Mtr.		
3	S&F, connecting and commissioning looping type cable end control box with 2mm fabricated CRCA sheet of size 200 mm x 200 mm x 125 mm having 1 no. 6amp to 32 amp SPMCB 250 volt and 2 nos. brass neutral link square rod 6 way and fixed on 5 mm thick bakelite sheet. Box shall have almirah type hing and panel key type lock front door duly painted with earthing strud etc. complete as required.	1.00	Nos.		
4	S/F, of 20mm of steel flexible pipe on surface/ open duct with all ancillaries and accessories like coupleretc. as required.	12.00	Mtr.		
5	S/F, copper cable lug suitable for 4/6 sqmm of conductor.	11.00	Nos.		
6	S/F, angle iron 40mm x 40mm x 6mm i/c cutting, welding, painting etc. as reqd	2.00	Mtrs.		

Unit Qty Description S.No. (in words & Figures) S/F testing commissioning of street light 7 Luminures Endura Pearl Neo - IP65 following LED light / flood light fitting New generation energy saving and environmental friendly long life LED street light made up of pressure die cast aluminium housing with high power LED as lighting source and lens embedded PC cover having TOP Opening seperate driver compartment with IP66 protection and impact resistance of IK07.,make:Phillips/Havells or its equvalent, on the existing street light pole complete as required. Nos. 6.00 50W Street light

Total Rs.

अभिनाती विकास (ति) / E.E. (Fleet.) भारतिकारिक भाग प्रीत स्थमनान् कानपुर I.W.D., LLT. Ker

Amount

Rate