

QUOTATION

Name of work:- Replacement of defective 250A MCCB in LT panel of Substation no.7 and Replacement / repairing of 11KV insulators 33KV busbar PG clamps and other associated works.

S.No.	Description of item	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Providing and fixing of 3pole, 36KA, 415V, 250A, MCCB , With Microprocessor Release Inbuilt instantaneous Protection Switchable thermal memory Variable trip class Front LED Indication and breaking capacity MCCB with rotary handle in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.make: L&T only cat No. CM920540000X1, TYPE-DN2250D	1.00	Each		
2	Supplying, fixing of Epoxy based busbar insulator for vacuum circuit braker required complete.	15.00	Each		
3	Supplying, fixing of Pad Clamp suitable for 33KV installation of ACSR panther conductor made of aluminium having 4nos holes including stainless steel nut-bolts, washer as required complete.	25.00	Each		
Total Rs.					_____



25/10/2023
अधीक्षक अभियन्ता / S.E.
संनिविदा (I.W.D.)
भा.प्रौ. संस्थान, कानपुर
I.I.T., Kanpur

