

QUOTATION

Sub:- Providing power points & internet points for wind tunnel in Old TA-202.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	80.00	Metre		
1.02	6 x 6 sq. mm	12.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	5.00	Meter		
3	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	26.00	Meter		
4	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
4.01	85 mm flexible cover	24.00	Meter		
4.02	End cap	8.00	Nos.		
4.03	Internal angles- adjustable from 80°-100°	1.00	Nos.		
4.04	separation partitions	20.00	Meter		
4.05	Joints for 85mm width cover	5.00	Nos.		
4.06	base joints	20.00	Nos.		
5	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
5.01	32 mm	10.00	Meter		

8

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
					(In words & Figures)
6	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
6.01	32 mm	45.00	Metre		
7	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	550.00	Meter		
8	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	9.00	Nos.		
9	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
9.01	Triple pole and neutral 5 A to 32 A	1.00	No.		
10	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
11	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
11.01	6 A switch	12.00	No.		
11.02	20 A switch	12.00	No.		

7

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
11.03	6 A pin 2/3 pin socket outlet	12.00	No.		
11.04	6/16 A 3 pin socket outlet	12.00	No.		
12	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
12.01	6 module	12.00	Nos.		

Total Rs.

[Handwritten Signature]

ॐ
 अधीकृत अधीक्षक/स.ई.
 सार्वजनिक (I.W.D.)
 भाजकीय संस्थाएं, कानपुर
 I.I.T., Kanpur
[Handwritten Signature]