

QUOTATION

Sub:- Renovation of store room to convert into an Office space near Karmchari Sangthan Office. (SH: Electrical Work)

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In Words & Figures)					
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
1.01	Group C	3.00	Point		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.01	3 x 1.5 sq. mm	15.00	Metre		
2.02	3 x 4 sq. mm	25.00	Metre		
3	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	25.00	Meter		
4	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
4.01	End cap	2.00	Nos.		
4.02	internal / external angle	4.00	Nos.		
4.03	changeable flat angle	3.00	Nos.		
4.04	flat junction	2.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In Words & Figures)	AMOUNT
5	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	1.00	No.		
6	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
6.01	1 X 20W Box type LED tube with fitting	2.00	Nos.		
7	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
7.01	5/6 A switch	5.00	No.		
7.02	15/16 A switch	2.00	No.		
7.03	3 pin 5/6 A socket outlet	2.00	No.		
7.04	6 pin 15/16 A socket outlet	2.00	No.		
8	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
8.01	3 Module	3.00	No.		
8.02	6 Module	1.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In Words & Figures)	AMOUNT
9	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
9.01	3 Module	3.00	Nos.		
9.02	6 Module	1.00	Nos.		
10	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
10.01	8 way , Double door	1.00	No.		
11	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
11.01	Single pole 5 A to 32 A	6.00	No.		
11.02	Double Pole (40A-63A)	1.00	Nos.		
12	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	1.00	Nos.		
13	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	2.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In Words & Figures)

14 Dismantling concealed & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the sectional store repairing the damages as reqd complete.

2.00

Nos.

15 Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.

3.00

No.

Total Rs.




 S. E.
 (L.W.D.)
 Kanpur
 I.T., Kanpur
