

**INDIAN INSTITUTE OF TECHNOLOGY KANPUR**  
**Dean of Infrastructure & Planning**

NIT No.- QT/03-04-2024-03

N/W P&F of CPVC piping with accessories on exposed wall from 6th floor to Gr. Floor for split AC Drain water line at FB-606, FB-609, FB-615, FB-619 etc.

S.NO.	Description	Qty	Unit	Rate	Amount
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold-water supply and all CPVC plain and brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in charge. (Internal work – Exposed on wall)				
2	32 mm nominal outer dia. pipes	99	Mtr		
		<b>Total in (Rs.)</b>			
		<b>Add GST</b>			
		<b>Grand Total in (Rs.)</b>			



**Dean of Infrastructure & Planning**