INDIAN INSTITUTE OF TECHNOLOGY KANPUR Dean of Infrastructure & Planning

NIT No.- QT/03-04-2024-05

N/W Replacement of defective starter with associated work installed at DT well no. 13 (near Health center)

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Supply, installation, testing and commissioning of 3_phase star-delta starter suitable for submersible pump motor of 30 HP capacity, 415 volts with single phase preventer etc. housed in metal enclosure with hinged door & lockable arrangement duly painted including connections complete as required. (Make L & T MU-G50 FASD or equivalent approved make.)	1	No.		
2	Supplying & drawing following sizes of FR PVC insulated copper conductor single core cable in the existing surface / recessed steel /PVC conduit as reqd.				
a)	4 x 16 sqmm	6	Mtrs.		
3	Supply and making end termination with copper lugs for following size of PVC insulated copper conductor cable complete as required as reqd.	2	set		
4	Dismantling old/damaged DB/TPN switch/ MCCB/ starter/ telephone DP in surface/ recessed including depositing the same in store as reqd.	1	No.		
	Sub-total Sub-total				
	Add_GST@				
	Total				

Dean of Infrastructure & Planning