

QUOTATION

Name of work: Electrical Maintenance work at south side residence as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	15.00	Nos.		
b)	15/16 Amp. switch	3.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	12.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	2.00	Nos.		
e	Bell push	1.00	Nos.		
2	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	46.00	Nos.		
b)	2 way 5/6 A switch	2.00	Nos.		
c)	15/16 Amp. switch	25.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	23.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	22.00	Nos.		
f)	Bell push	2.00	Nos.		
g)	Fan regulator socket type rotary step	6.00	Nos.		
3	Supply & fixing modular blanking plate on existng metal boxes but excluding modular plate as req.	29.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
4	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	1 or 2 module	3.00	Nos.		
b)	3 module	6.00	Nos.		
c)	4 module	15.00	Nos.		
d)	6 module	5.00	Nos.		
e)	8 module	3.00	Nos.		
f)	12 module	3.00	Nos.		
5	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	2.00	Nos.		
6	Supplying and fixing brass batten/ angle holder including connection etc. as required.	20.00	Nos.		
7	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	6.00	Nos.		
8	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a)	Single Pole	17.00	Nos.		
9	Supplying and fixing following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensitivity current up to 300 mA in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a)	40 Amp	1.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
b)	63 Amp	2.00	Nos.		
10	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
a)	8-way , Double door	2.00	Nos.		
11	Suply /fixing testing & ommissioning of 7 watt 1 feet or 2 fe Led wall/mirroe ligh equivalent approved make as required.	6.00	Nos.		
12	Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required complete etc as reqd	14.00	Nos.		
13	Supply and fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips) or its equivalent approved make as required.				
a)	LED bulb 5W to 10 W	6.00	Nos.		
b)	LED tube light 18 / 20 Watt.	4.00	Nos.		
14	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	1.00	Nos		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
15	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	Fan regulator socket type rotary step	5.00	Nos.		
16	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	13.00	Nos.		
17	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	16.00	Nos.		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	17.00	Nos.		
19	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1000.00	Sq.cm		

Total Rs

Kumar

अधिकाारी अधिकाारी (वि.वि.) ए.ए. (Elect.)/AC
 राजीवगान्धी, का.रा.रा. संस्थान, काठमाडौं
 I.W.D., I.L.L., K.पुष्प
Diya