

## QUOTATION

**Name work :** Repairing & temporary connection of faulty street light in area computer centre, ACES, WL, Pradhan gate to NCC gate as per enclosed complaints.

S.No.	Description	Qty	Unit	Rate	Amount
				(In Words & Figures)	
1	Laying of one no. PVC insulated and PVC sheathed /XLPE power cable of 1.1kV grade in the existing masonry open duct as reqd.				
a	Upto 35 sqmm	220.00	Mtr.		
2	Digging cable trench/lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	45.00	Mtr.		
3	Dismantling and refixing brass compression type gland up to 35 sq. mm. cable	40.00	Nos.		
4	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.				
a	upto 35 sqmm	11.00	Nos.		
5	Dismantling cross arm / street light brakcet/street light fitting from pole complete as required.	7.00	Nos.		

Total Rs.

  
क्रा.वि.स.सं. (वि.) / E.E. (Elect.)  
नामिका, आ. प्र. स.कान. कानपुर  
U.W.D., I.I.T. Kanpur

