

QUOTATION

Sub:- Shifting & providing three phase connection for fume hoods in Old SAC 'C' block.

S.No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.				
a	4 X 6 sq. mm + 2 X 6 sq. mm earth wire	90.00	Metre		
2	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	20.00	Meter		
3	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	85 mm flexible cover	20.00	Meter		
b	End cap	4.00	Nos.		
c	Internal angles- adjustable from 80°-100°	3.00	Nos.		
d	external angles- adjustable from 60°-120°	2.00	Nos.		
e	flat junction	3.00	Nos.		
f	flat angles	1.00	Nos.		
g	Joints for 85mm width cover	10.00	Nos.		
h	base joints	20.00	Nos.		
4	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				

S.No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	Double pole 5 A to 32 A	2.00	No.		
b	Triple pole and neutral 5 A to 32 A	4.00	No.		
c	Triple pole (40A-63A)	4.00	Nos.		
5	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	6.00	Nos.		
6	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	20.00	Nos.		
7	Providing connection for motor/ panel starter/ transformer upto 1 Kva / steblizer.	9.00	Nos.		
8	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
a	6 /10/16 Sq.mm.	24.00	Nos.		
9	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	15/16 A switch	4.00	No.		
b	6 pin 15/16 A socket outlet	4.00	No.		
10	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	3 Module	2.00	No.		
b	6 Module	1.00	No.		

S.No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
-------	-------------	-----	------	------------------------------	--------

11 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.

a	3 x 4 sq. mm	31.00	Metre		
b	3 x 6 sq. mm	30.00	Metre		

Total Rs.



अविभागी अमियन्ता (फि)/E.E. (Elect.)
 नगरपालिका, भाग फी. संस्थान, काठमाडौं
 स. नं. D.I.I.I. KATHMANDU

(Handwritten initials)