

QUOTATION

Sub:- Repairing & Replacement of electrical ite Wire,,DLP, Switch/socket, LED lights etc in IME Corridor, NWTF-301, Hiigh speed-01, CL-205E, Samtal Etc. and other labs & offices in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a	Group C	1.00	Point		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	1 x 1.5 sq. mm	40.00	Metre		
b	3 x 1.5 sq. mm	25.00	Metre		
c	3 x 2.5 sq. mm	2.00	Metre		
3	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required				
a	20 mm	12.00	Metre		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
4	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	44.00	Meter		
5	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	1.00	Meter		
6	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	85 mm flexible cover	0.50	Meter		
b	End cap	2.00	Nos.		
7	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	2.00	Meter		
b	25 mm	3.00	Meter		
8	Supply & Laying of 32 mm dia, 8Kg / cm ² , minimum 2.0 mm thick HDPE pipe, ISI mark in following manners as required complete.				
a	in open duct	6.00	Meter		
9	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required				

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	18 watt recess 300 x 300 mm mounting LED light fixture	9.00	Nos.		
b	36 watt recess mounting LED light fixture 600 x 600 mm	2.00	Nos.		
10	Supplying and fixing, following LED street light luminaries with pressure die cast aluminium IP65 housing, driver etc. complete with all accessories as required.				
a	45 Watt LED street light luminaries	1.00	Nos.		
11	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	11.00	No.		
b	15/16 A switch	2.00	No.		
c	3 pin 5/6 A socket outlet	3.00	No.		
d	6 pin 15/16 A socket outlet	2.00	No.		
e	Blanking Plate	3.00	No.		
12	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	1.00	No.		
13	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	lor 2 Module	3.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
b	3 Module	2.00	No.		
c	4 Module	1.00	No.		
d	6 Module	2.00	No.		
14	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	3.00	Nos.		
b	3 Module	1.00	Nos.		
c	6 Module	1.00	Nos.		
15	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor make as reqd complete.				
a	5 Amp	2.00	Nos.		
16	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	13.00	Nos.		
17	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	70.00	Meter		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
18	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
19	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	3.00	Nos.		
20	Supply Installation, testing and commissioning of following ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable etc. as required.				
a	1200mm sweep.	1.00	Nos.		
21	S & F fan hook I/c cutting the slab and fixing with the reinforcement and making damage, painting etc as the same	1.00	Nos.		
22	Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete.				
a	for 450 mm / 18" sweep	2.00	Nos.		
23	Supplying, installation, testing & commissioning of heat detector operating at 542C/572C with rate of rise cum fixed temperature (dual thermistor) type with mounting base complete with all connection etc. as required.	3.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
--------	-------------	-----	------	------------------------------	--------

24 Supplying, installation, testing & commissioning of smoke detector with builtin LED and mounting base complete with all connections etc. as required. 15.00 No.

25 Supplying, installation, testing & commissioning response indicator on surface/recess MS box having two LEDs metallic cover complete with all connections etc. as required. 1.00 No.

Total Rs.

[Handwritten Signature]

अभिषेक अभियंता (वि.)/E.E. (Elect.)
सतमिन्दि, भा. प्रौ. संस्थान, कानपुर
U.W.D., I.T., Kanpur

[Handwritten Signature]