


QUOTATION

Name of work: Replacement of UTP wire in H. No. 311 & 327 and electrical repairing works as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	3 x 1.5 Sq.mm..	8.00	Mtr.		
b)	3 x 4 Sq.mm..	6.00	Mtr.		
2	S & F metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in the front I/c painting etc as reqd.				
a)	100 mm x 100 mm x 60 mm deep	2.00	Nos.		
3	S & F following piano type switch / socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	2.00	Nos.		
b)	15/16 Amp. switch	1.00	Nos.		
c	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.		
d	Bell push	1.00	Nos.		
4	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	2.00	Nos.		
b)	3 Pin 5/6 Amp. socket outlet	2.00	Nos.		
5	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
a) 6	Module	1.00	Each		
6	Supplying and fixing brass batten/ angle holder including connection etc. as required.	1.00	Nos.		
7	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	1.00	Nos.		
8	Providing and fixing following sizes of PVC casing and capping on surface as reqd.	0.00			
a) 20 x 12 mm		15.00	Mtr.		
9	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	2.00	Nos.		
10	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	600.00	Sq.cm		
11	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	12.00	Nos.		
12	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	3.00	Nos.		
13	S & F following piano type switch / socket on existing switch box/cover I/c connection etc as reqd.				
a) Fan regulator socket type rotary/dimmer		1.00	Nos.		
14	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	350.00	Mtr.		
15	Supply and laying of HDPE pipe ISI mark of 25 mm (6Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a) Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.		135.00	Mtr.		

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
b)	In pipe	14.00	Mtr.		
c	On surface with MS clamp	1.00	Mtr.		
16	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a	40mm dia	14.00	Mtr.		
17	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
	Total Rs				


 अधिसूची अभियन्ता (वि.) / E.E. (Elect.)
 संगठनिका: वाठ प्रौ संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur
