

QUOTATION

Sub:- Replacement of damaged submain wire with 3.5 x 25 Sq.mm cable from Floor panel to DB of Lab No-107 New core Lab.

SL No.	DESCRIPTION	QTY	UNIT	RATE (In Words & Figures)	AMOUNT
1	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	2.00	Meter		
2	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
2.01	85 mm flexible cover	2.00	Meter		
2.02	End cap	2.00	Nos.		
3	Supplying and laying of one no. 3.5 x 25.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners.				
3.01	in open duct	55.00	Meter		
3.02	On Surface	10.00	Meter		
4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
4.01	3½ X 25 sq. mm (28mm)	2.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In Words & Figures)	AMOUNT
5	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	65.00	Meter		
6	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	2.00	Nos.		
7	Supplying and installing following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required.				
7.01	300 mm width X 50 mm depth X 1.6 mm thickness	45.00	Meter		

Total Rs.



अधिकाारी अभियंता (वि०) E.E. (Elect.
संनिवि०, भा०प्र० संस्थान, कानपुर
I W.D., I.I.T., Kanpur

