QUOTATION

Name of work -: Electrical maintenance work at south side residences and schools in the campus as per enclosed complaints.

S.No	Description	Qty	Unit	Rate	Amount
		Fe#		(In words & Figures)	
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
a	Group A	1.00	Points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.	ž.			
a	1 x 1.5 Sq.mm	24.00	Mtr.		
b	3 x 1.5 Sq.mm	10.00	Mtr.		
C	3 x 4 Sq.mm	13.30	Mtr.		
3	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	5/6 Amp switch	2.00	Nos.		
b	15/16 Amp. switch	1.00	Nos.		
c	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.	a	
4	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.			4	
a	5/6 Amp switch	18.00	Nos.		

S.N	o Description	Qty	Unit	Rate (In words & Figures)	Amount
b	2 way 5/6 amps switch	1.00	Nos.	(minoral di ilgales)	
c	15/16 Amp. switch	11.00	Nos.		
d	3 Pin 5/6 Amp. socket outlet	9.00	Nos.		
e	6 Pin 15/16 Amp. socket outlet.	11.00	Nos.		
f	Bell Push	2.00	Nos.		
g	Blanking plate	12.00	Nos.		
5	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a	1/2 module	1.00	Nos.		
b	3 module	6.00	Nos.		
c	6 module	2.00	Nos.		
d	12module	1.00	Nos.		
6	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as				
a	read. 1 or 2 module	1.00	Nos.		
b	3 module	4.00	Nos.		
c	6 module	1.00	Nos.		
d	8 module	2.00	Nos.	3	
	Supplying and fixing brass batten/ angle holder including connection etc. as required.	13.00	Nos.		
0	Supplying and fixing call bell/buzzer suitable for ac single phase, 230 volts, complete as required.	3.00	Nos.		

S.No	Description	Qty	Unit
9	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)		
a	16-way , Double door	1.00	Nos.
10	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.		
a	Single Pole	16.00	Nos.
11	Supplying and fixing following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection, testing & commissioning etc as reqd.	,	
a	63 Amp	2.00	Nos.
12	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.		
a	Fan regulator socket type rotary/dimmer	1.00	Nos.
13	Providing and fixing following sizes of PVC casing and capping on surface as reqd.		2(4))
a	20 x 12 mm	25.00	Mtr.
14	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.		

Rate

(In words & Figures)

Amount

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
a	Bulk head fitting suitable for 60W GLS lamp	1.00	Nos		
15	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a	1200 mm	4.00	Nos		
16	Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1600.00	Sq.cm		
17	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	10.00	Nos.		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	37.00	Nos.		
19	Dismentaling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	11.00	Nos.		
	Total De)

Total Rs.

A Property of the second secon