

QUOTATION


Name of work:- Electrical maintenance works at south side residences, VFA ,SBRA & Park-67 in the campus as per enclosed complaints.

| S.No. | Description | Qty. | Unit | Rate | Amount |
|-------|---|-------|------|------|----------------------|
| | | | | | (In Words & Figures) |
| 1 | Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd. | | | | |
| a) | 3 x 1.5 Sq.mm.. | 3.00 | Mtr. | | |
| b) | 3 x 4 Sq.mm.. | 20.00 | Mtr. | | |
| 2 | Supply and fixing of following sizes of medium class PVC conduit along with the accessories in surface /recess including cutting the wall and making good the same in case of recessed conduit as reqd. | | | | |
| a | 25mm | 10.00 | Mtr | | |
| 3 | S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd. | | | | |
| a) | 5/6 Amp switch | 6.00 | Nos. | | |
| b | 15/16 Amp. switch | 4.00 | Nos. | | |
| c) | 3 Pin 5/6 Amp. socket outlet | 4.00 | Nos. | | |
| d | 6 Pin 15/16 Amp. socket outlet. | 2.00 | Nos. | | |
| 4 | Supplying and fixing brass batten/ angle holder including connection etc. as required. | 3.00 | Nos. | | |
| 5 | Supplying and fixing call bell/ buzzer suitable for single phase,230 V, complete as required. | 1.00 | Nos. | | |

| S.No. | Description | Qty. | Unit | Rate | Amount |
|-------|---|---------|-------|----------------------|--------|
| | | | | (In Words & Figures) | |
| 6 | Providing and fixing following sizes of PVC casing and capping on surface as reqd. | | | | |
| a) | 20 x 12 mm | 1.00 | Mtr. | | |
| b) | 25 x 16 mm | 8.00 | Mtr. | | |
| 7 | Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd. | 4.00 | Nos. | | |
| 8 | S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd. | 1854.00 | Sq.cm | | |
| 9 | Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd. | 5.00 | Nos. | | |
| 10 | Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd. | 4.00 | Nos. | | |
| 11 | S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd. | | | | |
| a) | Fan regulator socket type rotary/dimmer | 5.00 | Nos. | | |
| 12 | Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete. | | | | |
| a | LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires wipro or its equivalent approved make etc as reqd | 3.00 | Nos. | | |

| S.No. | Description | Qty. | Unit | Rate | Amount |
|-------|--|-------|------|----------------------|--------|
| | | | | (In Words & Figures) | |
| b | LED tube light (1 X 20 Watt. LED) surface mounting luminaires wipro meke or equivalent approved make. | 3.00 | Nos. | | |
| 13 | S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd. | | | | |
| a) | 100 mm x 100 mm | 2.00 | Nos. | | |
| 14 | Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete. | | | | |
| a | Bulk head fitting suitable for 100W GLS lamp, Philips make or equivalent. | 2.00 | Nos | | |
| 15 | Supplying, fixing, connecting, testing & commissioning single phase electronic kWh meter LCD type of following ratings i/c. sealing the same (sealing material will be supplied by the dept.) etc as reqd. | | | | |
| a | 10-60 A, 230V, 50 Hz | 3.00 | Nos. | | |
| 16 | Supplying, fixing, cleaning, testing commissioning of 4 watt LED light/lamp make philips OR equivalent approved make. | 30.00 | Nos | | |

Total Rs.


 अधीक्षक अभियन्ता (विद्युत) / ए. ए. (विद्युत.)
 संयोजक, राग जी० संस्थान, काठमाडौं
 (W/O, I.T. KATHMANDU)