

QUOTATION

Sub:- Providing and making power , network & telephone points in KD-105, 106 & 107.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 2.5 sq. mm	10.00	Metre		
1.02	3 x 4 sq. mm	95.00	Metre		
2	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.01	2 Pair	15.00	Metre		
3	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	40.00	Meter		
4	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
4.01	End cap	3.00	Nos.		
4.02	internal / external angle	6.00	Nos.		
4.03	changeable flat angle	4.00	Nos.		
4.04	flat junction	1.00	Nos.		
5	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	8.00	Meter		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
6	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
6.01	85 mm flexible cover	7.00	Meter		
6.02	End cap	6.00	Nos.		
6.03	flat angles	1.00	Nos.		
7	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
7.01	2 module	1.00	Nos.		
7.02	3 module	4.00	Nos.		
7.03	6 module	1.00	Nos.		
8	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
8.01	6 A switch	3.00	No.		
8.02	20 A switch	3.00	No.		
8.03	6 A pin 2/3 pin socket outlet	3.00	No.		
8.04	6/16 A 3 pin socket outlet	3.00	No.		
8.05	RJ 11 Telephone socket	1.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
9	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	425.00	Meter		
10	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	10.00	Nos.		
11	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
11.01	32 mm	15.00	Metre		
11.02	40 mm	20.00	Metre		
12	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
12.01	Telephone socket outlet	1.00	No.		
12.02	Blanking Plate	2.00	No.		
13	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
13.01	lor 2 Module	1.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
14	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
14.01	1 or 2 Module	1.00	Nos.		
15.00	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
15.01	32 mm	5.00	Meter		
15.02	40 mm	5.00	Meter		
Total Rs.					_____

(Handwritten signature)

(Handwritten mark)
अधीक्षक अभियन्ता / S.E.
सोनिविठो (I.W.D.)
माओप्रौठो सस्थान, कानपुर
I.I.T., Kanpur
(Handwritten signature)