

## QUOTATION

Name of work :- Replacement of old & non functional energy meter with allied work in the campus as per enclosed complaints.

S.No	DESCRIPTION	Qty	Unit	Rate (In Words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
1.1	1 x 1.5 Sq.mm..	6.00	Mtr.		
2	Fixing & connecting 1/3 ph temporary service connection from supply source to desired place up to the lead of 50 Mtr. And dismantling the same form source i/c to & fro cartage. ( extension board and cable will be supplied by the dept.)	3.00	Nos.		
3	Dismantling damaged DB/TPN Switchs/KWH Meter loose wire boxes along with all accessories and depositing the same in the store as reqd.	5.00	Nos.		
4	Supplying, fixing, connecting,testing & commissioning LCD display three phase meter ( Cat No. WR301BC3C00, L&T 415V,50hz digital LCD multifunction KWH electronic meter i/c sealing the same(sealing material will be supplied by the dept.) Gurantee car having serial no. of the meter to be submitted in the dept. etc as reqd.	2.00	Nos.		

8

S.No	DESCRIPTION	Qty	Unit	Rate (In Words & Figures)	Amount
5	Supplying, fixing, connecting, testing & commissioning Dir operated LCD display three phase meter ( Cat No. WR301BC7D10, L&T 415V,50hz digital LCD multifunction KWH electronic meter i/c sealing the same(sealing material will be supplied by the dept.) Gurantee car having serial no. of the meter to be submitted in the dept. etc as reqd.	4.00	Nos.		
6	Reparing, servicing testing and commissioning 1 or 3 phase kWh meter I/c sealing the same (sealing material will be supplied by the dept.	1.00	Nos.		
<b>Total Rs.</b>					_____

*Spine*

2  
 अधीक्षक अभियन्ता / S.E.  
 संचालित (स.स.स.)  
 भा.प्री. संस्थान का.प.प.र.  
 I.I.T., Kanpur *Net*