

INDIAN INSTITUTE OF TECHNOLOGY KANPUR

Dean of Infrastructure & Planning

NIT No.- QT/25-06-2024-02

Providing and fixing of outdoor signages at various locations of IIT Kanpur campus

Fill up here



| SLNo | Description | Qty | Unit | Estimated Rate without GST (Rs) | Estimated Amount without GST (Rs) | Quoted Rate without GST (Rs) | Quoted Amount without GST (Rs) |
|----------|--|-----|------|---------------------------------|-----------------------------------|------------------------------|--------------------------------|
| 1 | MINOR CIVIL MAINTENANCE WORK: | | | | | | |
| 1.1 | Providing & fixing Signage of size 48x24 Inch material used 304 Grade and 16 Gauge Stainless Steel etc complete as directed by the Engineer-in-charge. | 1 | each | 28800.00 | 28800.00 | | |
| 1.2 | Providing & fixing Signage of size 12x6 Inch with 3mm Aluminium Composite Panel (ACP) Sheet and 3M Ratro sheet having a minimum thickness of 90 microns with fluoroscent letters pasted on ACP sheet i/c fixing of signages with SS studs of suitable size i/c drilling holes and fixing etc. complete as per approved sample | 4 | each | 720.00 | 2880.00 | | |
| 1.3 | Providing & fixing Signage of size 8x412x6 Inch with 3mm Aluminium Composite Panel (ACP) Sheet and 3M Ratro sheet having a minimum thickness of 90 microns with fluoroscent letters pasted on ACP sheet i/c fixing of signages with SS studs of suitable size i/c drilling holes and fixing etc. complete as per approved sample | 1 | each | 320.00 | 320.00 | | |
| 1.4 | Providing and fixing signage of size 18x24 Inch with 5mm Sunboard sheet with UV Printing etc. complete as directed by Engineer -in-charge | 6 | each | 2592.00 | 15552.00 | | |
| | | | | Estimated Amount (A) = | 47552.00 | Quoted Amount (B) = | Rs. |
| | | | | Percentage (%) = | $\frac{B-A}{A} \times 100$ | | |

Dean, Infrastructure and Planning

[Handwritten Signature]
25/06/24