


## QUOTATION

**Sub :-Providing and making power outlet for computer in UAV Lab near Airstrip.**

SL No.	DESCRIPTION	QTY	UNIT	Estimated Rate without GST	Estimated Amount without GST
1.00	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
1.01	Group C	4.00	Point	783.87	3135.47
2.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.01	3 x 1.5 sq. mm	200.00	Metre	83.30	16659.36
2.02	3 x 4 sq. mm	15.00	Metre	180.62	2709.34
3.00	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
3.01	20 mm	5.00	Metre	195.53	977.64
4.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	22.00	Meter	1014.47	22318.28
5.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
5.01	85 mm flexible cover	20.00	Meter	447.17	8943.45
5.02	End cap	2.00	Nos.	202.54	405.09
5.03	Internal angles- adjustable from 80°-100°	5.00	Nos.	559.40	2797.02
5.04	external angles- adjustable from 60°-120°	2.00	Nos.	572.56	1145.11
5.05	flat junction	1.00	Nos.	974.13	974.13
5.06	flat angles	4.00	Nos.	790.88	3163.52
5.07	Joints for 85mm width cover	8.00	Nos.	232.35	1858.83
5.08	base joints	16.00	Nos.	92.94	1487.07
6.00	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				

SL No.	DESCRIPTION	QTY	UNIT	Estimated Rate without GST	Estimated Amount without GST
6.01	Single pole 5 A to 32 A	2.00	No.	224.46	448.93
7.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
7.01	36 watt surface mounting LED light fixture 300 x 1200 mm	4.00	Nos.	6001.75	24007.01
8.00	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	6.00	Nos.	99.96	599.74
9.00	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
9.01	6 A switch	45.00	No.	244.63	11008.33
9.02	20 A switch	1.00	No.	442.79	442.79
9.03	6 A pin 2/3 pin socket outlet	45.00	No.	291.98	13138.97
9.04	6/16 A 3 pin socket outlet	1.00	No.	569.93	569.93
10.00	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
10.01	3 module	15.00	Nos.	313.02	4695.31
10.02	6 module	16.00	Nos.	419.11	6705.83
				<b>Estimated Amount</b>	<b>128191.14</b>
				<b>Please quote percentage above / below (%) =</b>	
				<b>Quoted Amount (Rs.)</b>	

  
 28/10/2024  
 ताल्लुरि केशवदास  
 TALLURI KESAVADAS  
 अधिशासी अभियंता (विद्युत)  
 Executive Engineer (Elect)  
 स.पि.सि. भा.सं. संस्था, बंगलूर  
 I.W.D., I.I.T. K.