

QUOTATION

Sub:- Providing and making input and output connection for 10 KVA single phase to single phase UPS at MFCM building lab no.-301.

S.No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 16 sq.mm.	45.00	Meter	631.30	28408.59
2.00	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	5.00	Meter	191.14	955.72
3.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.01	separation partitions	12.00	Meter	201.67	2419.99
4.00	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
4.01	32 mm	16.00	Metre	285.84	4573.43
5.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
5.01	6 /10/16 Sq.mm.	12.00	Nos.	34.20	410.35
6.00	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
6.01	32 mm	5.00	Meter	84.17	420.87
7.00	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
7.01	Single Pole (40A-63A)	1.00	Nos.	456.82	456.82

