


QUOTATION

Sub:-	Providing and making additional power outlets at DJAC 605 HF.				
SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 2.5 sq. mm	20.00	Metre	120.12	2402.46
1.02	3 x 4 sq. mm	175.00	Metre	180.62	31608.94
2.00	Supply and drawing PVC insulated 3 core round copper conductor cable of following size for connection of equipment / exhaust fan etc as reqd.				
2.01	4.00 sq. mm	20.00	Meter	201.67	4033.32
3.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	30.00	Meter	770.71	23121.44
4.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
4.01	85 mm flexible cover	28.00	Meter	339.32	9501.10
4.02	End cap	6.00	Nos.	156.95	941.69
4.03	Internal angles- adjustable from 80°-100°	8.00	Nos.	427.01	3416.05
4.04	external angles- adjustable from 60°-120°	7.00	Nos.	452.43	3167.03
4.05	flat junction	1.00	Nos.	753.18	753.18
4.06	flat angles	1.00	Nos.	608.51	608.51
4.07	separation partitions	5.00	Meter	201.67	1008.33
4.08	Joints for 85mm width cover	12.00	Nos.	170.98	2051.73
4.09	base joints	24.00	Nos.	75.41	1809.73
5.00	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
5.01	25 mm	5.00	Meter	71.90	359.49
6	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
6.01	6 A switch	26.00	No.	162.21	4217.45
6.02	20 A switch	13.00	No.	277.07	3601.93
6.03	6 A pin 2/3 pin socket outlet	26.00	No.	183.25	4764.58
6.04	6/16 A 3 pin socket outlet	23.00	No.	350.72	8066.64

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7.00	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
7.01	3 module	5.00	Nos.	248.14	1240.68
7.02	6 module	17.00	Nos.	323.54	5500.22
					112174.48
	Estimated Amount Rs.				112174.00
	Quoted percentage Above or below				
	Quoted Amounts Rs.				

Bidder Signature with date

Bidder Seal


 17/06/22
 ताल्लुरि केशवदास
 TALLURI KESAVADAS
 अधिशासी अभियंता (विद्युत)
 Executive Engineer (Elect)
 रा. व. वि. मा. प्रौ. संस्थान, कानपुर
 I.V.D., I.I.T. Kanpur