


QUOTATION

Name of work:- Replacement of Oil leakage & damaged outdoor type oil cooled 33KV CT rating 600-300-150/5-5-5A for 33KV/11KV substation.

S.N	Description of item	Qty	Unit	Rate	Amount
1	Supply fixing, testing, commissioning of outdoor type, oil cooled 33KV substation current transformer (CT) rating: 600-300-150/5-5-5A live tank, burden 30VA, class :0.5/10P10/PS, Burden-30VA, having following specification In confirmation to IS: 2705/ 1992 as directed by Engineer in-charge.				
	CT specification:				
	1. Type: OCT-33, AD. 600-300-150/5-5-5 Amp				
	2. Core.I Burden 30VA class 0.5				
	Core-II Burden 30VA class 10P10				
	Core-III burden 30VA class PS nee point voltage 50Volt				
	3. BIL 36/75/1750KV				
	4. Ith: 13.1KA/3sec				
	5. Iex: 150mA at Vk/4	3.00	Nos.	55880.00	167640.00
2	Supplying and erection of ACSR conductor of 54 x 3.18 mm aluminium and 7 x 3.18 mm dia steel reinforced (Zebra conductor) on 33 kV over head line including binding, fittings, clamps etc as required complete.	10.00	Mtr.	1006.00	10060.00
3	Supplying, fixing of PG Pad Clamp suitable for 33KV installation of ACSR panther conductor made of aluminium having 4nos holes including stainless steel nut-bolts, washer as required complete.	10.00	Each	1881.00	18810.00
4	Supplying, fixing Gun fitting for Zebra Conductor including nut-bolts, washer as required complete.	10.00	Nos.	3205.00	32050.00
	Total Estimated Rs.				2,28,560.00
	Quoted Percentage Above / below percentage				
	Quoted Amount Rs.				

Bidder Signature & Date

Bidder Seal


विनय कुमार तिवारी
(VINAY KUMAR TIWARI)
 अधिरक्षक अभियंता (वि०) E.E. (Elect.)
 संवि० वि०, मा० प्र० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur