


## QUOTATION

**Name of Work :** Providing and fixing 15 Ampere switch and socket for Air Curtain at GH-1 and Providing a separate power supply for RO in all blocks of Hall-14 and other associated works.

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor single core cable in / on the existing surface / recessed, PVC / steel conduit as reqd.				
(a)	3 x 4 Sq.mm..	295.00	Mtr.	180.62	53282.90
2	S & F following size/module, GI box along with modular base and cover plate for modular switches in recess as required.				
(a)	1/2 module (1 or 2 module)	2.00	Nos.	261.28	522.56
(b)	3 module	1.00	Nos.	286.72	286.72
3	Supply and & fixing following modular switch/ socket on the existing modular plates & switch box including connection but excluding modular plate etc. as reqd.				
(a)	15/16 Amp. one way switch	2.00	Nos.	136.78	273.56
(b)	6 Pin 15/16 Amp. socket outlet.	2.00	Nos.	172.73	345.46
4	S & F MCB of following pole and rating 240/415 volts 'C' series in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand)				
(a)	Single Pole 6 amp to 32 amp	15.00	Nos.	224.46	3366.90
5	Providing & fixing of size 32 mm x 12.5 mm. DLP mini trunking system with independent cover as reqd.	236.00	Mtrs	156.03	36823.28
6	Providing & fixing accessories for 32 mm x 12.5 mm size of DLP mini trunking system as reqd.				
(a)	Flat junction	2.00	Nos.	133.24	266.48
(b)	Changeable flat angle	49.00	Nos.	107.82	5283.13
(c)	Changeable internal / External angle	113.00	Nos.	101.68	11490.18
(d)	End cap left or right	39.00	Nos.	77.14	3008.42
	Estimate Amount Rs.				114949.59
	Say Rs.				114950.00
	Quoted percentage Above/Below=				
	Quoted Amount Rs.				

Bidder Signature & Date

Bidder Seal

  
**TALLURI KESAVADAS**  
 अधिकांशी अभियंता (विद्युत)  
 Executive Engineer (Elect)  
 स.मि.वि. वा.डी. संभाग, कावपुर  
 I.W.D., I.I.T. Kaspur  
