


QUOTATION

Name of work: Providing additional wall mounting revolving fan with allied works in Room No. 400, 402 at DoMS in Academic Area in the campus at IIT Kanpur.

| S. No. | Description | Qty. | Unit | Estimated rate without GST | Estimated Amount without GST |
|--------|--|-------|------|----------------------------|------------------------------|
| 1 | Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd. | | | | |
| a) | 3 x 1.5 sq. mm | 85.00 | Mtr. | 83.30 | 7080.23 |
| 2 | Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete. | 75.00 | Mtr | 228.48 | 17135.82 |
| 3 | Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system. | | | | |
| a) | End cap | 20.00 | Nos. | 152.32 | 3046.37 |
| b) | internal / external angle | 10.00 | Nos. | 148.41 | 1484.13 |
| c) | changeable flat angle | 2.00 | Nos. | 124.98 | 249.96 |
| d) | flat junction | 1.00 | Nos. | 146.46 | 146.46 |
| 4 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. | | | | |
| a) | 5/6 A switch | 18.00 | No. | 88.85 | 1599.34 |
| b) | 3 pin 5/6 A socket outlet | 18.00 | No. | 104.47 | 1880.55 |
| 5 | Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required. | | | | |
| a) | 1 or 2 Module | 6.00 | No. | 113.26 | 679.57 |
| b) | 3 Module | 20.00 | No. | 129.86 | 2597.22 |
| 6 | Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required. | | | | |
| a) | 1 or 2 Module | 6.00 | Nos. | 297.80 | 1786.81 |
| b) | 3 Module | 20.00 | Nos. | 316.35 | 6327.07 |

| S. No. | Description | Qty. | Unit | Estimated rate without GST | Estimated Amount without GST |
|---|--|-------|------|----------------------------|------------------------------|
| 7 | Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete. | 23.00 | Nos. | 2695.84 | 62004.33 |
| Estimated Amount Rs. | | | | | 106017.86 |
| Say Rs. | | | | | 106018.00 |
| Please quote percentage above/below(%) = | | | | | |
| Quoted Amount Rs. | | | | | |


 21/02/25
 ताल्लुरि केशवदास
 TALLURI KESAVADAS
 अधिशाही अभियंता (विद्युत)
 Executive Engineer (Elect)
 सं.वि.वि. मा.प्रौ. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur
