


QUOTATION

Name of work :- Providing Copper earthing in Old Core Lab. 103C and WLE- 215 with all allied works as required in Academic area as per enclosed DOIP form 101 requested by User in the campus at IIT Kanpur.

Sl. No	Description	QTY	Unit	Rate	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	3 x 4 sq. mm	10.00	Metre	180.62	1806.23
b)	3 x 6 sq. mm	10.00	Metre	266.55	2665.50
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.				
a)	40 mm	15.00	Mtr.	541.03	8115.52
3	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	58.00	Metre	1385.36	80350.72
4	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	15.00	Mtr	228.48	3427.16
5	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
a)	End cap	6.00	Nos.	152.32	913.91
b)	internal / external angle	6.00	Nos.	148.41	890.48
c)	changeable flat angle	3.00	Nos.	124.98	374.94
d)	flat junction	2.00	Nos.	146.46	292.92
6	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
a)	32 mm	2.00	Mtr	81.04	162.08
7	Chemical Earthing with Copper bonded rod of copper coating of 250 microns of dia 25 mm, length 3 Mtr with clamp, including earth enhancement material and RCC precast Pit cover and earthing pit etc as reqd. complete.	3.00	No.	9778.65	29335.94
	Estimated Amount Rs.				128335.40
	Say Rs.				128335.00
	Please quote percentage above/below(%) =				
	Quoted Amount Rs.				


T. Kesavadas
TALLURI KESAVADAS
अभियंता (विद्युत)
Executive Engineer (Elect)
च.नि.वि. मा.प्र. संस्थान, काणपुर
I.W.D., I.I.T. Kanpur