


QUOTATION

Name of work:- Repairing and Servicing of 500KVA DG set installed Outreach centre NOIDA.

S.N	Description of item	Qty	Unit	Estimated rate without GST	Estimated Amounts without GST
1	Servicing & testing of 500KVA DG set installed Outreach centre NOIDA complete by replacing following items as directed by Engineer In-charge.				
a	Element Pre fuel Filter	2.00	each	211.00	422.00
b	Element to Air Filter 105413100107	2.00	each	5089.00	10178.00
c	Element Micro fuel Filter	2.00	each	180.00	360.00
d	Greaves Lub.Oil 20 L CI-4	2.00	each	6755.00	13510.00
e	Greaves Lub.Oil 10 L CI-4	1.00	each	3392.00	3392.00
f	Greaves Lub.Oil CI-5 Ltr. Pack	1.00	each	1725.00	1725.00
g	LUB Oil Filter 234	1.00	each	4048.00	4048.00
h	Hose Thermostat to radiator A Bank-84	1.00	each	389.00	389.00
i	Hose Thermostat to radiator B Bank-94	1.00	each	450.00	450.00
j	Fuel Pipe FIP to Filt A Bank Motorpal	1.00	each	301.00	301.00
k	Vent Pipe B Bank	2.00	each	3241.00	6482.00
l	Emergency Stop PB-(Mushroom)	1.00	each	405.00	405.00
m	Copper _ Washer	8.00	each	7.00	56.00
n	DSE Controller	1.00	each	43711.00	43711.00
o	Magn. Pick Up	1.00	each	3932.00	3932.00
p	Fuel Filling Cap with Key	1.00	each	590.00	590.00
q	Packing and Forwarding	1.00	each	2000.00	2000.00
2	Servicing, Repairing checking , cleaning fixing/dismantling of spare parts and testing of 500KVA DG set as per complete requirment as per instructed by Engineer Incharge.	2.00	Day	9000.00	18000.00
	Estimated Amount Rs. (A)				109951.00
	CP @15% of A (B)				16492.65
	Total Rs.(A+B)				126443.65
	Say Rs.				126444.00
	Please quote percentage above/below(%) =				
	Quoted Amount Rs.				


 08/03/25
 ताल्लूरि केशवादास
 TALLURI KESAVADAS
 अभियंता अभियंता (विद्युत)
 Executive Engineer (Elect)
 स.नि.वि. भा.प्रौ. संस्थान, काठपुर
 I.W.D., I.I.T. Kanpur
