

QUOTATION

Name of Work : Replacement of defective power supply cable from switchroom to C-Block Ground Floor Hall-9 and other associated works.

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Supplying of PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size 3-1/2x120 sqmm.	69.00	Mtr.	679.75	46903.06
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
(a)	Above 95 sq. mm and upto 185 sq. mm	50.00	Mtr.	436.62	21830.78
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.				
(a)	Above 95 sq. mm and upto 185 sq. mm	5.00	Mtr.	79.67	398.33
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
(a)	Above 95 sq. mm and upto 185 sq. mm	14.00	Mtr.	65.18	912.55
5	Supplying and making end termination with brass compression gland, aluminium lugs for following size of PVC insulated & PVC sheathed / XLPE aluminium cable of 1.1kV grade as reqd.				
(a)	3-1/2x120 sq.mm.	2.00	Nos.	634.23	1268.46
6	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required.				
(a)	100 mm dia	3.00	Mtrs	1868.55	5605.65
	Total Estimated Rs.(i/c GST)				76918.83
	Say Rs.(i/c GST)				76919.00
	Quoted Percentage Above/ below				
	Quoted Amount Rs.(i/c GST)				

Bidder Signature & Date

Bidder Seal


TALLURI KESAVADAS
 अधिष्ठापी अभियंता (विद्युत)
 Executive Engineer (Elect)
 सं. वि. वि. मा. वि. संस्थान, जयपुर
 U.P.D., I.I.T. Kanpur
