

QUOTATION

Name of work:- Replacement of 11KV panel indoor CT 400-200/1-1A in the feeder of Substation No. 12 at substation no. 1

S.N	Description of item	Qty	Unit	Rate	Amount
1	Supply fixing, testing, commissioning of Indoor type, resin cast 11KV substation current transformer (CT) rating: 400-200/1-1A , burden 15VA, class :1, having following specification In confirmation to IS: 3156/1992	6.00	Nos.	8074.00	48444.00
	Estimated Amount Rs.				48,444.00
	Please quote percentage above/below (%)				
	Quoted Amounts Rs.				

T. K. K.
24/4/25
TALLURI KESAVADAS
Executive Engineer (Elect)
W.D. & M. S. Dept., W.P.
I.W.D., I.I.T. Kanpur
Dale