

## QUOTATION


**Name of Work : Renovation of rooms in Block-C and Block-D at SIIC Extension (SH-Electrical Work)**

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor single core cable in / on the existing surface / recessed, PVC / steel conduit as reqd.				
(a)	3 x 1.5 Sq.mm..	159.00	Mtr.	81.21	12912.26
(b)	3 x 4 Sq.mm..	79.00	Mtr.	176.09	13910.83
2	S & F following size/module, GI box along with modular base and cover plate for modular switches in recess as required.				
(a)	1/2 module (1 or 2 module)	30.00	Nos.	254.72	7641.66
(b)	3 module	29.00	Nos.	279.52	8106.18
(c)	6 module	16.00	Nos.	343.63	5498.12
(d)	8 module	1.00	Nos.	388.08	388.08
3	S & F following size modular base and cover plate for following modular metal boxes etc as required.				
(a)	8 module	3.00	Nos.	180.37	541.10
4	Supplying and fixing wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
(a)	100 mm x 100 mm	30.00	Nos.	113.09	3392.65
5	Supply and & fixing following rating piano type switch / socket / fan regulator on the existing switch box/cover I/c connection etc. as reqd.				
(a)	5/6 amp one way switch	13.00	Nos.	44.45	577.79
(b)	Two way 5/6 amp switch	2.00	Nos.	54.70	109.40
(c)	15/16 amp one way switch	2.00	Nos.	103.44	206.87
(d)	3/5 pin 5/6 Amp. Socket outlet.	3.00	Nos.	58.98	176.94
(e)	6 pin 15/16 Amp. Socket outlet	2.00	Nos.	117.10	234.21
(f)	Batten Holder/ Angle Holder Bakelite	94.00	Nos.	60.44	5681.72
(g)	Ceiling rose 3-Pin, 5A	30.00	Nos.	74.37	2230.96
(h)	Fan regulator socket type (step type)	3.00	Nos.	224.23	672.68
6	Supply and & fixing following modular switch/ socket on the existing modular plates & switch box including connection but excluding modular plate etc. as reqd.				
(a)	5/6 Amp one way switch	91.00	Nos.	88.04	8011.93
(b)	15/16 Amp. one way switch	2.00	Nos.	133.35	266.69
(c)	3 Pin 5/6 Amp. socket outlet	63.00	Nos.	104.29	6569.96
(d)	6 Pin 15/16 Amp. socket outlet.	4.00	Nos.	168.39	673.58
(e)	Modular Type Electronic Fan regulator	2.00	Nos.	315.42	630.84
(f)	Modular type blanking plate.	6.00	Nos.	34.19	205.14



Sl. No.	Item Description	Qty.	Units	Rate	Amount
7	Supply, Installation, testing & commissioning of AC ceiling fan of following sweeps, aluminium die cast body , copper wound, double bearing, less 70 watts 220 volts 50 Hz without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd. ( ISI marked.)				
(a)	1200 mm Make_Bajaj Kassel/ or approved Make.	20.00	Nos.	2347.56	46951.18
8	Supplying and fixing following rating and pole, 240/440 V, residual current circuit breaker (RCCB), having a sensitivity current 300 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
(a)	40 amp double pole RCCB	1.00	Nos.	3684.15	3684.15
9	Supply, fixing, testing & commissioning MCB of following pole and rating 240/415 volts 'C' curve 10kA in the existing MCB DB complete as reqd. ( legrand or approved Make)				
(a)	Triple Pole 40 amp to 63 amp	1.00	Nos.	2369.98	2369.98
10	Supply,Installation,Testing and commissioning of batten fitting ,4 ft long (without lamps) including connection,nut bolts, washer and screw etc. after removing old complete as required.				
(a)	Batten for LED tube T8 (PC_Body) suitable Make Crompton-(ECO) or approved make)	29.00	Nos.	489.40	14192.59
11	Supply,Installation,Testing and commissioning LED down light,mirror & bulk head light fittings (integrated type) including connection,nut bolts, washer and screw etc. after removing old complete as required.				
(a)	LED Ceiling/down Light 12 watt surface type. Make_Philiphs (sleek_surface) or approved Make	17.00	Nos.	1144.53	19457.05
12	Supply, Fixing,Testing and commissioning of following lamps and choke (copper/Electronic ballast) in existing old fittings including connection etc. complete as required.				
(a)	LED PC Tube rod 20 watt,T8 ,4 ft long,doube/single sided inbuilt driver (Make_Havells Maxoled or as per approved make)	47.00	Nos.	240.80	11317.61
13	Dismantling and refixing of wooden board of any sizes on surface or in recessed etc as reqd.	1.00	Nos.	123.81	123.81
14	Fixing PVC/MS / data box/ router box of any size on surface/recessed including painting, making good with enamel paint etc. as reqd.	1.00	Nos.	90.67	90.67
15	Providing & fixing of size 32 mm x 12.5 mm. DLP mini trunking system with independent cover as reqd.	169.00	Mtrs	180.36	30480.25
16	Providing & fixing of accessories for 105 mm x 50 mm size of DLP trunking system as reqd.				

Sl. No.	Item Description	Qty.	Units	Rate	Amount
(a)	Flexible cover for 85 mm width	1.00	Mtr	465.03	465.03
(b)	End Caps	13.00	Nos.	209.60	2724.85
17	Dismantling and re-fixing of any size ceiling fan (at normal height) complete including connection as required.	7.00	Nos.	122.84	859.86
18	S & F of following size of medium class PVC conduit along with the accessories in surface/ recess I/c cutting the wall and making good the same in case of recessed conduit as reqd.				
(a)	20 mm 16 SWG	1.00	Mtr.	109.41	109.41
	Estimated Amount				211466.05
	Say Rs.				2,11,466.00
	Please quote percentage above/below( %) =				
	Quoted Amount Rs.				

  
 T. Kesavadas  
 02/05/25  
 TALLURI KESAVADAS  
 अधिशासी अभियंता (विद्युत)  
 Executive Engineer (Elect)  
 इ.पि.वि. भा.प्रौ. संस्थान, कानपुर  
 I.W.D., I.I.T. Kanpur  
