


## QUOTATION

**Name of work:-** Fault Identification / Repairing of damaged second source service cable of Hall-8, SIDBI, Block-A (Hall-11).

S.N	Description of item	Qty	Unit	Rate	Amount
1	Digging cable trench/lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	100.00	Mtr.	148.18	14818.06
2	Lifting removing cable up to 400sq.mm. size from trench/clamps, making role & depositing the same in store I/c cartage.	30.00	Mtr	141.17	4234.98
3	Locating fault of by using fault locating machine for 0.433/11KV cable ( HT/LT cable ) in the cable lines meggaring etc and rectifying removing & restoring the same and making good the damages cable etc as directed by the Engineer Incharge.	4.00	Each	13357.30	53429.20
4	Dismantling and refixing of brass compression type gland up to 400 sq. mm. cable	5.00	Each	205.17	1025.87
	Estimated Amount				73508.11
	Say Rs.				73508.00
	Please quote Percentage above /below				
	Quoted Amount Rs.				

  
TALLURI KESAVADAS  
अभिनेता अभियंता (सि.ए.)  
Executive Engineer (Sect)  
सि.पि.अ. भवन, वाराणसी  
I.W.D., I.I.T. Kanpur  
