

QUOTATION

Sub:- **Providing and making additional three phase and single phase power points and other associated work in DJAC-102.**

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	65.00	Metre	180.62	11740.46
1.02	6 x 6 sq. mm	80.00	Metre	524.33	41946.51
2	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
2.01	Triple pole 5 A to 32 A	3.00	No.	882.95	2648.84
2.02	Triple pole and neutral 5 A to 32 A	3.00	No.	1076.72	3230.16
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
3.01	6 pin 15/16 A socket outlet	1.00	No.	172.73	172.73
4	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
4.01	for 2 Module	1.00	No.	116.62	116.62
5.00	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	15.00	Meter	228.48	3427.16
6.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
6.01	End cap	2.00	Nos.	152.32	304.64
6.02	internal / external angle	2.00	Nos.	148.41	296.83
6.03	changeable flat angle	2.00	Nos.	124.98	249.96

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	11.00	Meter	990.07	10890.77
8.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
8.01	85 mm flexible cover	11.00	Meter	436.45	4800.96
8.02	End cap	1.00	Nos.	198.21	198.21
8.03	Internal angles- adjustable from 80°-100°	2.00	Nos.	545.81	1091.62
8.04	external angles- adjustable from 60°-120°	1.00	Nos.	559.48	559.48
8.05	flat junction	1.00	Nos.	951.99	951.99
8.06	flat angles	1.00	Nos.	772.33	772.33
8.07	Joints for 85mm width cover	5.00	Nos.	227.50	1137.51
8.08	base joints	10.00	Nos.	90.81	908.05
9.00	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
9.01	25 mm	5.00	Meter	69.32	346.62
9.02	32 mm	5.00	Meter	81.04	405.21
10.00	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	3.00	Nos.	920.75	2762.24
11.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
11.01	for 2 Module	1.00	Nos.	297.80	297.80
12.00	Supply fixing connecting & commissioning of 5 Amp rating ISI marked 3 pin Plug top Anchor make as reqd complete.	1.00	Nos.	108.38	108.38
13.00	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
13.01	375 mm / 15" sweep	1.00	Nos.	5553.76	5553.76
14.00	Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete.				

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
14.01	for 375 mm / 15" sweep	1.00	Nos.	869.97	869.97
15.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
15.01	6 /10/16 Sq.mm.	36.00	Nos.	34.17	1230.26
16.00	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
16.01	6 A switch	6.00	No.	239.22	1435.31
16.02	20 A switch	8.00	No.	432.55	3460.36
16.03	6 A pin 2/3 pin socket outlet	6.00	No.	285.11	1710.65
16.04	6/16 A 3 pin socket outlet	7.00	No.	556.55	3895.84
17.00	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
17.01	4 module	1.00	Nos.	332.95	332.95
17.02	6 module	6.00	Nos.	410.09	2460.53
	Total Estimated Rs.				110314.70
	Please Quote percentage Above /below				110315.00
	Quoted Amount Rs.				

Bidders Signature
with Seal & Date.

T. K. Kesava Das
22/05/22
TALLURI KESAVADAS
अधीनस्थ अभियंता (विद्युत)
Executive Engineer (Elect)
च.नि.वि. वा.प्र. विभाग, कर्पुर
I.W.D., I.L.T. Karpur
(Seal)