

QUOTATION

Name of Work: Repair/overhauling/rewinding of Air curtain & its allied electrical works in mess of Hall-8, 10, 14 and other hostels in IIT Kanpur.

Sl. No.	Item Description	Quantity	Units	Rate	Total Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor single core cable in / on the existing surface / recessed, PVC/ steel conduit as reqd.				
a)	3 x 1.5 Sq.mm..	50.00	Mtr.	102.97	5148.51
b)	3 x 4 Sq.mm..	40.00	Mtr.	219.80	8792.08
2	Supply and & fixing following modular switch/ socket on the existing modular plates & switch box including connection but excluding modular plate etc. as reqd.				
a)	5/6 Amp one way switch	10.00	Nos.	119.80	1198.02
3	Cleaning of air curtain of any size installed in kitchen/mess area including opening cabinet, bearings, checking, cleaning, greasing, replacing rubber rings, nut bolts, hander clamps, bearing plates, cutter pin etc. if required reassembling, testing & commissioning complete as required.	1.00	Nos.	796.00	796.00
4	Overhauling of air-curtain of any size including dismantling and re-fitting the unit with rag bolts, checking, clening, oiling greasing, replacement of defective spares etc. (Extra cost will be paid against used new parts after submitted bill). reassembling the air curtain testing and commissioning as reqd..	1.00	Nos.	1050.00	1050.00
5	Rewinding of air curtain motor with copper wire i/c dismantling cutting the damaged winding and providing rewinding along with insulation paper, varnish, connecting copper leads of suitable quality including dismentling and refixing from normal/abnorml height and refixing as required.(old burnt wire shall be retain by the contactor.)	19.00	Nos.	1691.00	32129.00
	Total Estimated Rs. (i/c GST)				49113.61
	Say Rs.(I/c GST)				49,114.00
	Quoted Percentage Above/Below				
	Quoted Amount Rs.				

Bidder Signature & Date

Bidder Seal


TALLURI KESAVADAS
 अधिष्ठायी अभियंता (विद्युत)
 Executive Engineer (Elect)
 सं.वि.वि. मा.प्रौ. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur