

QUOTATION

Name of work:-Supplying & laying of 5 paired jelly filled telephone cable from 100 pair Telephone DB near N0.665 to House N0.4090 Type-IV

S.No.	Description	Qty.	Unit	Rate	Amount
1	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
1.1	40 mm dia	16.00	Mtr.	626.00	10016.00
2	S&L, connecting and commissioning following 5 pairs jelly filled armoured telephone cable PVC insulated and PVC sheathed annealed tinned copper conductor.				
2.1	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	116.00	Mtr.	604.00	70064.00
2.2	In pipe	12.00	Mtr.	198.00	2376.00
2.3	In open duct	1.00	Mtr.	187.00	187.00
2.4	On surface with MS clamp	1.00	Mtr.	215.00	215.00
3	Fixing Telephone DP upto 5/10/20/50/100 pairs on wall/ floor with required nut bolts/fixing arrangements as required complete.	2.00	Nos.	321.00	642.00
	Total Estimated				83500.00
	Quoted Percentage Above/Below				
	Quoted Amount Rs (i/c GST)				

Bidder Signature & Date

Bidder Seal


 24/08/20

TALLI SINGH KEDAR BHAS
 ASSISTANT ENGINEER (Civil)
 Executive Engineer (Civil)
 R.M.B. & B. & B. & B. & B.
 L.W.D. L.L.T. & B. & B.

24/8/20