

QUOTATION

Name of Work : Supplying and installation of energy meter in Hall-13 office with other associated works.

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Supplying and drawing following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
(a)	2 x 6 sq. mm	3.00	Meter	234.00	702.00
(b)	3 x 6 sq. mm	3.00	Meter	326.00	978.00
2	Supplying and fixing DP sheet steel enclosure on surface/ recess along with 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	1.00	Each	1258.00	1258.00
3	Providing & fixing of size 32 mm x 12.5 mm. DLP mini trunking system with independent cover as reqd.	5.00	Meter	192.00	960.00
4	Providing & fixing accessories for 32 mm x 12.5 mm size of DLP mini trunking system as reqd.				
(a)	Flat Junction	2.00	Each	151.00	302.00
(b)	Changeable Flat Angle	2.00	Each	118.00	236.00
(c)	Changeable Internal/External Angle	2.00	Each	111.00	222.00
(d)	End cap left or right	2.00	Each	84.00	168.00
5	Supplying and fixing single phase kWh energy meter with LCD Display with meter box, class 1 Base Mounting of following rating and specification including connection complete as required.				
(a)	Single Phase LCD Meter 10-60A.	1.00	Each	2100.00	2100.00
6	Dismantling and refixing of existing Distribution Board with connection complete as required.	1.00	Each	125.00	125.00
	Tota Estimate Rs (i/c GST)				7,051.00
	Quoted Percentage Above/Below				
	Quoted Amount Rs (i/c GST)				

Bidder Signature & Date

Bidder Seal


 17/09/2026
प्रदीप कुमार
(PRADEEP KUMAR)
 अधिशासी अभियंता (वि.) EE (Elect.)
 विद्युत विभाग. (Elect. Divn.)
 सं० नि० वि०, भा० प्र० संस्थान कानपुर
 I. W. D., I. I. T. Kanpur - 18
 14/09/26