QUOTATION

Name of Work : Supplying, Laying, Testing and Commissioning of cable for providing DG supply to street lights.

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Supplying & Laying of one no. XLPE cable aluminium conductor steel armoured cable of size 3-1/2 x 70sqmm, grade 1.1kV in following manners.				
(a)	In Ground I/c excavation, sand cushioning protective covering, refilling of earth as reqd.	1.00	Mtr.	1268.00	1,268.00
(b)	In existing Pipe	72.00	Mtr.	863.00	62,136.00
(c)	In existing open duct	68.00	Mtr.	848.00	57,664.00
(d)	Fixing on surface with MS clamp	1.00	Mtr.	889.00	889.00
2	Supplying and Laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers, end cap etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.				
(a)	Direct in ground (75 cm below ground level) including excavation, sand cushioning, protective covering and refilling the trench etc complete as required	75.00	Meter	534.00	40,050.00
(b)	In existing Pipe	1.00	Meter	192.00	192.00
(c)	In existing open duct	1.00	Meter	135.00	135.00
(d)	Fixing on surface with MS clamp	1.00	Meter	251.00	251.00
3	Supplying and making indoor end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1kV grade as reqd.				
(a)	3-1/2x70 sqmm(38mm)	2.00	Set	536.00	1,072.00
	Total Estimated Rs. (i/c GST)				**1,63,657.00**
	Quoted Percentage Above /below				
	Quoted Amount Rs.(i/c GS)				

29/10/2025

प्रदीप कुमार
(PRADEEP KUMAR)
अधिशाषी अभियंता (वि.). EE (Elect.)
विद्युत विभाग. (Elect.Divn.)
सं० नि० वि०, भा० प्रौ० संस्थान कानपुर
I. W. D., I. I. T. Kanpur - 16

28/10/25

Bidder Signature & Date

Bidder Seal