INDIAN INSTITUTE OF TECHNOLOGY, KANPUR
INSTITUTE WORKS DEPARTMENT
ELECTRICAL DIVISION

No. ED/EE/2026 /283 Dated: 06/11/2026

QUOTATION NOTICE

M/s .....
.....
.....

Dear Sirs,

Sealed quotations are invited from the eligible electrical contractor by the undersigned on behalf of the Director, IIT Kanpur, "**Providing electrical power supply with allied works as required for STP (~~Sewage~~ Sewage Treatment plant) at Hall of Residence No. 14 in the campus.** As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 17-11-2026 up to 12.00 PM and the quotation will be opened on the same day at 3.30 PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

1. The quotations should be submitted in a properly sealed envelope, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelope. Bidder has to drop his quotation in a sealed cover at the Drop box available at office only. Otherwise offers shall not be considered for further evaluation.

2. The contractor should have the following documents and must enclose the relevant copies.

   (i) Registration Certificates of EPF & ESIC.
   (ii) "A" class Electrical License.
   (iii) GST Registration & PAN Card

3. The time allowed for carrying out the above noted work is 28 (Twenty-Eight) Days.

4. Security @ 7.50% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.

5. The estimated cost of quotation is Rs. 1,46,148/- (i/c GST) , Earnest Money of Rs. 2,922/- is to be submitted in the form of FDR pledged in favour of the Director,IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one months's time.

6. The quotations shall remain valid for 90 days from the date of opening.

7. Income tax & Trade tax will be recovered as per Government norms from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.

8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.

9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.

10. The material should be used as per enclosed approved list of make.

11. Penalty 1% per week may be imposed on delay completion of the work.

QUOTATION

Name of work: Providing electrical power supply with allied works as required for STP (Sewage Treatment plant) at Hall of Residence No. 14 in the campus.

S. No.	Description	Qty.	Unit	Rate	Amount (Rs.)
1	Supplying & Laying of one no. XLPE power cables (heavy duty) PVC sheathed working voltage upto, including 1100 volts, aluminium conductor steel armoured cable confirming to IS1554 (Part-1) & 7098 (Part-1) cable of size **3-1/2 x 95**sqmm, grade 1.1kV in following manners.				
a)	In Ground I/c excavation, sand cushioning protective covering, refilling of earth as reqd.	69.00	Mtr.	1474.00	101706.00
b)	In existing Pipe	8.00	Mtr.	1064.00	8512.00
c)	In existing open duct	2.00	Mtr.	1049.00	2098.00
d)	Fixing on surface with MS clamp	1.00	Mtr.	1143.00	1143.00
2	Supplying and making indoor end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1kV grade as reqd.				
a)	3-1/2x95 sqmm(45mm)	2.00	Set	684.00	1368.00
3	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	80mm dia	8.00	Mtr.	1041.70	8333.60
4	Supplying, connecting and commissioning of following size aluminium bus bar including bending to suitable shape, making hole for nut-bolts, providing and fixing bus bar insulators, slivering, nut-bolts in existing panel/box for connections etc. as required complete.				
a)	1 x 25mm x 6mm	2.00	Mtr.	425.00	850.00
5	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 Meter long etc. with charcoal/ coke and salt as required.	2.00	Set	8351.00	16702.00

S. No.	Description	Qty.	Unit	Rate	Amount (Rs.)
6	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	25.00	Meter	160.00	4000.00
7	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	5.00	Meter	287.00	1435.00
	Total Rs				146147.60
	Total Estimate Rs. (i/c GST)				146148.00
	Quoted percentage Above/Below				
	Quoted Amount Rs.				

Bidder Signature & Date

06/11/2024

प्रदीप कुमार
(PRADEEP KUMAR)
अधिशाषी अभियंता (वि.). EE (Elect.)
विद्युत विभाग. (Elect.Divn.)
सं0 नि0 वि0, भा0 प्रौ0 संस्थान कानपुर
I. W. D., I. I. T. Kanpur - 16
6/11/24

Bidder Seal