


QUOTATION

Sub:- Providing and making 40 kVA, 3 Phase stablizer input and output connection at Old Core Lab Extension 302H and other associated works.					
SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(i/c GST)	(i/c GST)
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	55.00	Metre	213.00	11715.00
1.02	2 x 10 sq.mm.	32.00	Meter	343.00	10976.00
1.03	6 x 10 sq.mm.	16.00	Meter	934.00	14944.00
2.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	7.00	Meter	909.00	6363.00
3.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.01	85 mm flexible cover	7.00	Meter	401.00	2807.00
3.02	End cap	2.00	Nos.	185.00	370.00
3.03	flat angles	1.00	Nos.	720.00	720.00
3.04	Joints for 85mm width cover	2.00	Nos.	202.00	404.00
3.05	base joints	4.00	Nos.	91.00	364.00
6.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
6.01	6 /10/16 Sq.mm.	20.00	Nos.	37.00	740.00
7.00	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
7.01	Four Pole (40A-63A)	1.00	Nos.	2020.00	2020.00
	Total Estimated Rs.				51423.00
	Say Rs.(i/c GST)				
	Quoted Percentage Above /Below				
	Quoted Amount Rs.(i/c GST)				

Bidder Signature & Date

Bidder Seal


ताल्लुरि केशवदास
TALLURI KESAVADAS
अधिराशी अभियंता (विद्युत)
Executive Engineer (Elect)
स.नि.वि. भा.प्री. संस्थान, कानपुर
I.W.D., I.I.T. Kanpur