

QUOTATION

Name of Work: Replacement and fixing of switch/socket/tubelight/fans in Reading room of Hall-4 and Hall-5 & Tracing of underground laid telephone cable loop near old VH extension Office..


Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor single core cable in / on the existing surface / recessed, PVC / steel conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	70.00	Mtr.	98.00	6860.00
2	Supply and & fixing following rating <i>piano type switch</i> /socket /fan regulator on the existing switch				
2.1	Ceiling rose 3-Pin, 5A	24.00	Nos.	90.00	2160.00
3	Supply and & fixing following <i>modular switch/ socket on the existing modular plates</i> & switch box including connection but excluding modular plate etc. as reqd.				
3.1	5/6 Amp one way switch	32.00	Nos.	107.00	3424.00
3.2	15/16 Amp. one way switch	3.00	Nos.	161.00	483.00
3.3	3 Pin 5/6 Amp. socket outlet	7.00	Nos.	126.00	882.00
3.4	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.	204.00	612.00
3.5	Modular Type Electronic Fan regulator	6.00	Nos.	382.00	2292.00
3.6	Modular type blanking plate.	2.00	Nos.	41.00	82.00
4	S & F following size/module, GI box along with <i>modular base and cover</i> plate for modular switches in recess as required.				
4.1	6 module	4.00	Nos.	416.00	1664.00
4.2	8 module	2.00	Nos.	470.00	940.00
4.3	12 module	3.00	Nos.	566.00	1698.00
5	Supply and fixing of 32 x 12.5 mm DLP mini- trunking white-system with independent cover etc. as required complete.	35.00	Meter	172.00	6020.00
6	Supply and fixing of following accessories suitable for 32 mm x 12.5 mm size plastic trunking white system.				
6.1	End cap	6.00	Nos.	74.00	444.00
6.2	internal / external angle	10.00	Nos.	103.00	1030.00
6.3	changeable flat angle	3.00	Nos.	112.00	336.00
6.4	flat junction	2.00	Nos.	141.00	282.00

Sl. No.	Item Description	Qty	Units	Rate	AMOUNT
7	Supply, Installation, testing & commissioning of AC ceiling fan of following sweeps, aluminium die cast body , copper wound, double bearing, less 70 watts 220 volts 50 Hz without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd. (ISI marked.)				
7.1	1400 mm Make_Bajaj Kassel/or approved Make.	8.00	Nos.	3212.00	25696.00
8	Supply,Installation,Testing and commissioning LED light fittings integrated (with lamps) including connection,nut bolts, washer and screw etc. after removing old complete as required.				
8.1	LED light fitting 20 watt with AL-Batten, Crompton or	20.00	Nos.	1076.00	21520.00
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
9.1	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	0.25	Cum.	7547.00	1886.75
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level in				
10.1	Cement mortar 1:6 (1 cement : 6 coarse sand).	0.25	Cum	9421.00	2355.25
11	Providing 12 mm cement plaster in fine sand of mix : 1:6 (1 cement: 6 fine sand) at all levels	1.00	Sqm	345.00	345.00
12	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.In cement mortar.	0.25	cum	2132.00	533.00
13	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge. All kinds of soil cum	2.00	cum	184.00	368.00

Sl. No.	Item Description	Qty	Units	Rate	AMOUNT
14	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	2.00	cum	203.00	406.00
15	Fixing of surface/ recess mounting Telephone DB. (DB will be provided by Telephone Exchange)	1.00	Each	461.00	461.00
	Total Rs.				82780.00
	Total Estimated Rs.(i/c GST)				82,780.00
	Quoted percentage Above / Below				
	Quoted Amount Rs.(i/c GST)				

Bidder signature & Date

Bidder Seal


 ताल्लूरि केशवदास
 TALLURI KESAVADAS
 अधिशासी अभियंता (विद्युत)
 Executive Engineer (Elect)
 स.मि.वि. भा.पौ. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur