

QUOTATION

Sub:- Replacement of defective electrical items like LED lights, fans, Laying of cable etc in NCL-204, KD-105, RM 4th floor, EC Lab, NCL-301, 302A, B etc other labs and offices in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE (i/c GST)	AMOUNT
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 1.5 sq. mm	10.00	Metre	98.29	982.90
2.00	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	5.00	Meter	225.55	1127.75
3.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
3.01	End cap	1.00	Nos.	147.95	147.95
3.02	internal / external angle	1.00	Nos.	140.71	140.71
3.03	changeable flat angle	1.00	Nos.	118.98	118.98
4.00	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
4.01	20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube	30.00	Nos.	371.43	11143.01
5.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
5.01	1 X 20W Box type LED tube with fitting	11.00	Nos.	982.90	10811.92
5.02	2 X 20W Box type LED tube with fitting	2.00	Nos.	1387.44	2774.89
5.03	18 watt recess 300 x 300 mm mounting LED light fixture	35.00	Nos.	1317.09	46098.11
5.04	18 watt surface mounting 300 x 300 mm LED light fixture	3.00	Nos.	1317.09	3951.27
5.05	36 watt recess mounting LED light fixture 600 x 600 mm	19.00	Nos.	3030.44	57578.41
5.06	36 watt surface mounting LED light fixture 300 x 1200 mm	1.00	Nos.	4161.30	4161.30
5.07	36/40 watt batten type LED light fixture	1.00	Nos.	646.65	646.65
6.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
6.01	5/6 A switch	1.00	No.	106.57	106.57
6.02	3 pin 5/6 A socket outlet	1.00	No.	126.23	126.23
7.00	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
7.01	3 Module	1.00	No.	156.23	156.23
8.00	Supplying and fixing following size/ modules, plastic-box for modular switches in recess etc as required.				
8.01	3 Module	1.00	Nos.	341.43	341.43
9.00	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantling & refixing as reqd.	14.00	Nos.	190.37	2665.22
10.00	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	74.00	Nos.	122.09	9034.42

SL No.	DESCRIPTION	QTY	UNIT	RATE (i/c GST)	AMOUNT
11.00	Supplying and fixing following capacity capacitor suitable for ceiling fan / exhaust fan / air-curtain etc..				
11.01	2.5 mfd	1.00	Nos.	132.43	132.43
12.00	Repairing of housing for bearing side /bush side /in fan body in ceiling fan /exhaust fan /rally fan etc.	1.00	Nos.	303.15	303.15
13.00	Rewinding of exhaust fans of following sizes i/c dismantling cutting the damaged winding and providing rewinding along with insulation paper, varnish, connecting copper leads of suitable quality including dismantling and refixing from normal/abnormal height and refixing as required.(old burnt wire shall be retain by the contactor.)				
13.01	Rewinding of exhaust fan 12"	1.00	Nos.	1490.91	1490.91
14.00	Carriage of Ceiling fan and regulator / exhaust fan from store to site as reqd.	1.00	Nos.	39.32	39.32
15.00	Supplying and fixing, following LED street light luminaries with pressure die cast aluminium IP65 housing, driver etc. complete with all accessories as required.				
15.01	45 Watt LED street light luminaries	2.00	Nos.	4139.57	8279.14
16.00	Dismantling the old conduit pipe/wood batten of all sizes from surface/recessed & making good the damages I/c filling the holes of the surface etc as reqd. and depositing it in sectional store.	70.00	Meter	39.32	2752.13
17.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.				
17.01	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	70.00	Metre	134.50	9415.17
	Total Esimated				174526.19
	Total Esimated Rs.				174526.00
	Quoted Percentage Above /Below				
	Quoted Amount Rs.(i/C GST)				


ताल्लुरि केशवदास
TALLURI KESAVADAS
 अधिशापी अभियंता (विद्युत)
 Executive Engineer (Elect)
 जं.नि.वि. मा.प्री. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur